

SUMMARY OF QUANTITIES

F&P NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	71BR	RANDOLPH	4	73
STA.	TO STA.			
CONTRACT NO.: 76125				

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X071-2A	SFTY-3M
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	543	543	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	486		486
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	486		486
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50	50	
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	10	10	
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	10	10	
* 72900200	METAL POST - TYPE B	FOOT	45	45	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3213	3213	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1285	1285	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	13	13	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	6	6	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	106	106	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12	
X0323500	REUSEABLE ENERGY ADOORBING CRASH TERMINAL (TEMPORARY)	EACH	1	1	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	237	237	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1	
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
Z0002600	BAR SPLICERS	EACH	808	808	
* Z0008318	DRILLED SHAFT IN ROCK 18"	FOOT	18	18	
* Z0008224	DRILLED SHAFT IN SOIL 24"	FOOT	85.9	85.9	
* Z0008242	DRILLED SHAFT IN SOIL 42"	FOOT	267.8	267.8	
* Z0008336	DRILLED SHAFT IN ROCK 36"	FOOT	190.4	190.4	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
51205200	TEMPORARY SHEET PILING	SQ FOOT	1597.2	1597.2	
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TL 2	EACH	1		1

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT				