FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
586	60R-2,37R-1	MADISON	502	38
STA.		TO STA.		
CONTRACT NO: 76301				

SEEDING SCHEDULE

LOCATION STA - STA	SIDE LT / R	SEEDING, CLASS 1A (ACRE)	SEEDING, CLASS 2 (ACRE)	NITROGEN FERT. NUTRIENT (LB)	PHOSPHORUS FERT. NUTRIENT (LB)	POTASSIUM FERT. NUTRIENT (LB)	MULCH, METHOD 2 (ACRE)	TEMPORARY EROSION CONTROL SEEDING (LB)
IL 162 4-LANE								
508+00 - 510+50	RT	0.23		20.7	20.7	20.7	0.23	23
	LT	0.17		15.3	15.3	15.3	0.17	17
510+50 - 513+00	RT	0.11		9.9	9.9	9.9	0.11	11
	LT	0.11		9.9	9.9	9.9	0.11	11
513+00 - 515+50	RT	0.12		10.8	10.8	10.8	0.12	12
	LT	0.16		14.4	14.4	14.4	0.16	16
515+50 - 518+65	RT	0.14		12.6	12.6	12.6	0.14	14
	LT	0.16		14.4	14.4	14.4	0.16	16
OMISSION								
531+97 - 533+00	RT	0.04		3.6	3.6	3.6	0.04	4
	LT	0.05		4.5	4.5	4.5	0.05	5
533+00 - 535+50	RT	0.07		6.3	6.3	6.3	0.07	7
	LT	0.05		4.5	4.5	4.5	0.05	5
535+50 - 538+00	RT	0.05		4.5	4.5	4.5	0.05	5
	LT	0.05		4.5	4.5	4.5	0.05	5
538+00 - 540+50	RT	0.06		5.4	5.4	5.4	0.06	6
	LT	0.05		4.5	4.5	4.5	0.05	5
540+50 - 543+00	RT	0.09		8.1	8.1	8.1	0.09	9
	LT	0.08		7.2	7.2	7.2	0.08	8
543+00 - 545+50	RT	0.08		7.2	7.2	7.2	0.08	8
	LT	0.08		7.2	7.2	7.2	0.08	8
545+50 - 548+00	RT	0.09		8.1	8.1	8.1	0.09	9
	LT	0.07		6.3	6.3	6.3	0.07	7
548+00 - 550+74	RT	0.06		5.4	5.4	5.4	0.06	6
	LT	0.08		7.2	7.2	7.2	0.08	8
550+74 - 553+25	RT	0.04		3.6	3.6	3.6	0.04	4
	LT	0.02		1.8	1.8	1.8	0.02	2
553+25 - 556+00	RT	0.07		6.3	6.3	6.3	0.07	7
	LT	0.04		3.6	3.6	3.6	0.04	4
556+00 - 558+50	RT	0.06		5.4	5.4	5.4	0.06	6
	LT	0.05		4.5	4.5	4.5	0.05	5
558+50 - 561+00	RT	0.08		7.2	7.2	7.2	0.08	8
	LT	0.06		5.4	5.4	5.4	0.06	6
561+00 - 563+50	RT	0.05		4.5	4.5	4.5	0.05	5
	LT	0.18		16.2	16.2	16.2	0.18	18
563+50 - 566+00	RT	0.07		6.3	6.3	6.3	0.07	7
	LT	0.1		9	9	9	0.1	10
566+00 - 568+50	RT	0.06		5.4	5.4	5.4	0.06	6
	LT	0.12		10.8	10.8	10.8	0.12	12
568+50 - 571+00	RT	0.07		6.3	6.3	6.3	0.07	7
	LT	0.1		9	9	9	0.1	10
571+00 - 573+52	RT	0.06		5.4	5.4	5.4	0.06	6
	LT	0.04		3.6	3.6	3.6	0.04	4
4-LANE SUBTOTAL		3.52		316.8	316.8	316.8	3.52	352
573+52 - 576+00	RT	0.05		4.5	4.5	4.5	0.05	5
	LT	0.03		2.7	2.7	2.7	0.03	3
576+00 - 578+50	RT	0.05		4.5	4.5	4.5	0.05	5
	LT	0.05		4.5	4.5	4.5	0.05	5
578+00 - 581+00	RT	0.02		1.8	1.8	1.8	0.02	2
	LT	0.03		2.7	2.7	2.7	0.03	3
581+00 - 584+00	RT	0.01		0.9	0.9	0.9	0.01	1
	LT	0.02		1.8	1.8	1.8	0.02	2
2 LANE SUBTOTAL		0.26		23.4	23.4	23.4	0.26	26

LOCATION STA - STA	SIDE LT / R	SEEDING, CLASS 1A (ACRE)	SEEDING, CLASS 2 (ACRE)	NITROGEN FERT. NUTRIENT (LB)	PHOSPHORUS FERT. NUTRIENT (LB)	POTASSIUM FERT. NUTRIENT (LB)	MULCH, METHOD 2 (ACRE)	TEMPORARY EROSION CONTROL SEEDING (LB)
IL 162 (CENTER ST)								
608+00 - 609+25	RT		0.01	0.9	0.9	0.9	0.01	1
	LT		0.01	0.9	0.9	0.9	0.01	1
609+25 - 615+00	RT		0.26	23.4	23.4	23.4	0.26	26
	LT		0.2	18	18	18	0.2	20
615+00 - 621+00	RT		0.37	33.3	33.3	33.3	0.37	37
	LT		0.62	55.8	55.8	55.8	0.62	62
621+00 - 627+00	RT		0.43	38.7	38.7	38.7	0.43	43
	LT		0.25	22.5	22.5	22.5	0.25	25
627+00 - 633+00	RT		0.1	9	9	9	0.1	10
	LT		0.15	13.5	13.5	13.5	0.15	15
633+00 - 639+00	RT		0.35	31.5	31.5	31.5	0.35	35
	LT		0.27	24.3	24.3	24.3	0.27	27
639+00 - 645+00	RT		0.42	37.8	37.8	37.8	0.42	42
	LT		0.38	34.2	34.2	34.2	0.38	38
645+00 - 651+00	RT		0.36	32.4	32.4	32.4	0.36	36
	LT		0.34	30.6	30.6	30.6	0.34	34
651+00 - 657+00	RT		0.33	29.7	29.7	29.7	0.33	33
	LT		0.27	24.3	24.3	24.3	0.27	27
657+00 - 663+00	RT		0.33	29.7	29.7	29.7	0.33	33
	LT		0.37	33.3	33.3	33.3	0.37	37
663+00 - 668+00	RT		0.27	24.3	24.3	24.3	0.27	27
	LT		0.27	24.3	24.3	24.3	0.27	27
668+00 - 674+00	RT		0.29	26.1	26.1	26.1	0.29	29
	LT		0.3	27	27	27	0.3	30
674+00 - 680+00	RT		0.3	27	27	27	0.3	30
	LT		0.31	27.9	27.9	27.9	0.31	31
680+00 - 686+00	RT		0.33	29.7	29.7	29.7	0.33	33
	LT		0.35	31.5	31.5	31.5	0.35	35
686+00 - 692+00	RT		0.26	23.4	23.4	23.4	0.26	26
	LT		0.39	35.1	35.1	35.1	0.39	39
692+00 - 698+00	RT		0.35	31.5	31.5	31.5	0.35	35
	LT		0.39	35.1	35.1	35.1	0.39	39
698+00 - 704+00	RT		0.34	30.6	30.6	30.6	0.34	34
	LT		0.34	30.6	30.6	30.6	0.34	34
704+00 - 710+00	RT		0.38	34.2	34.2	34.2	0.38	38
	LT		0.4	36	36	36	0.4	40
710+00 - 716+00	RT		0.3	27	27	27	0.3	30
	LT		0.6	54	54	54	0.6	60
716+00 - 719+45	RT		0.05	4.5	4.5	4.5	0.05	5
	LT		0.45	40.5	40.5	40.5	0.45	45
2 LANE RURAL SUBTOTAL			12.49	1124.1	1124.1	1124.1	12.49	1249
TOTAL		3.78	12.49	1464.3	1464.3	1464.3	16.27	1628

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SEEDING SCHEDULE

FAP ROUTE 586 (IL 162)
SECTION 60R-2,37R-1
MADISON COUNTY

DRAWN BY:

PLOT DATE: Friday July 02, 2004 @ 7:22:39 AM

PLAN | NOTE BOOK NO. | SURVEYED | PLOTTED | ALIGNMENT CHECKED | R/L OF WAY CHECKED | CADD FILE NAME | BY | DATE

7/2/2004
Friday July 02, 2004 @ 7:22:39 AM
c:\pwworking\dot\d0586\tmp\tmp0586pwdgn
LV-1-63