

# SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
604	120TS	MADISON	37	3
STA.		TO STA.		
CONTRACT NO.: 76798				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE 1000-1A	90% FED. 5% STATE 5% COUNTY Y031-1F
X3500146	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 3/4"	SQ YD	1064	1064	
X3500152	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 11 1/4"	SQ YD	166	166	
20200100	EARTH EXCAVATION	CU YD	762	762	
25000210	SEEDING, CLASS 2A	ACRE	0.9	0.9	
25100105	MULCH, METHOD 1	ACRE	0.9	0.9	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28000300	TEMPORARY DITCH CHECKS	EACH	30	30	
28000500	INLET AND PIPE PROTECTION	EACH	6	6	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	38.7	38.7	
35300605	PORTLAND CEMENT CONCRETE BASE COURSE 11 1/4"	SQ YD	45	45	
40000030	AGGREGATE (PRIME COAT)	TON	9.6	9.6	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	267	267	
40600990	TEMPORARY RAMP	SQ YD	21	21	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	10.2	10.2	
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	SQ YD	3414	3414	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	123	123	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	874	874	
44003800	MEDIAN SURFACE REMOVAL	SQ FT	15	15	
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	25	25	
44213200	SAW CUTS	FOOT	200	200	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2658	2658	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	13	13	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	1279	1279	
54213450	END SECTIONS 15"	EACH	10	10	
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	99	99	
60107600	PIPE UNDERDRAINS 4"	FOOT	140	140	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	49	49	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE 1000-1A	90% FED. 5% STATE 5% COUNTY Y031-1F
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	282	282	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5074	5074	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	144	144	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	47	47	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	34		34
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	259	259	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8398	8398	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	470	470	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	693	693	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	144	144	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	118	118	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32	32	
80300100	LOCATING UNDERGROUND CABLE	FOOT	100		100
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	286		286
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	19		19
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1126		1126
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	137		137
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	10		10
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	57		57
81018800	CONDUIT PUSHED, 3 1/2" DIA., GALVANIZED STEEL	FOOT	308		308
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	10		10
81400500	CONCRETE HEAVY-DUTY HANDHOLE	EACH	7		7
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1		1
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1417		1417
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
85800300	FLASHER CONTROLLER, WITHOUT CABINET	EACH	1		1
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2966		2966
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1862		1862
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1147		1147
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2368		2368

1/7/2005  
Friday, January 07, 2005 @ 11:26:21 AM  
C:\pwork\604\plan\sum1102576.dwg L:\1-63

\*SPECIALTY ITEMS

Rev.

PLOT DATE: Friday January 07, 2005 @ 11:26:21 AM