

CODE NO.	DESCRIPTION	UNIT	90% FED. 10% STATE		CONSTRUCTION TYPE CODE		
			TOTAL QTYS	J000-2A	X220-2A FRONTAGE ROAD BRIDGE	Y030-1E	Y002-1C
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,601	1,601			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	345	345			
20101000	TEMPORARY FENCE	FOOT	6,782	6,782			
20101100	TREE TRUNK PROTECTION	EACH	82	82			
20200100	EARTH EXCAVATION	CU YD	176,334	176,334			
20200200	ROCK EXCAVATION	CU YD	4,131	4,131			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	156,095	156,095			
20400800	FURNISHED EXCAVATION	CU YD	86,648	86,648			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,965	1,965			
20800150	TRENCH BACKFILL	CU YD	1,186	1,186			
20900110	POROUS GRANULAR BACKFILL	CU YD	2,885	2,885			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	46,477	46,477			
21101815	COMPOST FURNISH AND PLACE, 4"	SO YD	252,164	252,164			
* 25000210	SEEDING, CLASS 2A	ACRE	30.6	30.6			
* 25000310	SEEDING, CLASS 4	ACRE	39.9	39.9			
* 25000322	SEEDING, CLASS 5A	ACRE	39.9	39.9			
25000350	SEEDING, CLASS 7	ACRE	13.2	13.2			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8,262	8,262			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8,262	8,262			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8,262	8,262			
(2) 25000775	SELECTIVE MOWING STAKES	EACH	217	217			
(3) 25001810	SEEDING, CLASS 5 (SPECIAL)	ACRE	5.5	5.5			

CODE NO.	DESCRIPTION	UNIT	90% FED. 10% STATE		CONSTRUCTION TYPE CODE		
			TOTAL QTYS	J000-2A	X220-2A FRONTAGE ROAD BRIDGE	Y030-1E	Y002-1C
* 25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	6.7	6.7			
* 25100115	MULCH, METHOD 2	ACRE	21.7	21.7			
* 25100630	EROSION CONTROL BLANKET	SO YD	171,413	171,413			
25200200	SUPPLEMENTAL WATERING	UNIT	20	20			
28000300	TEMPORARY DITCH CHECKS	EACH	351	351			
28000510	INLET FILTERS	EACH	42	42			
28100105	STONE RIPRAP, CLASS A3	SQ YD	354	354			
28100107	STONE RIPRAP, CLASS A4	SQ YD	380	380			
28100109	STONE RIPRAP, CLASS A5	SQ YD	147	147			
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SO YD	2,193	2,193			
28300400	AGGREGATE DITCH	TON	805	805			
31200100	STABILIZED SUB-BASE 4"	SO YD	92,967	92,967			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TONS	139	139			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
42000531	PORTLAND CEMENT CONCRETE PAVEMENT 11 1/2" (JOINTED)	SO YD	30,795	30,795			
42001165	BRIDGE APPROACH PAVEMENT	SO YD	413			413	
42001300	PROTECTIVE COAT	SO YD	49,428	49,428			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	44	44			
44000007	BITUMINOUS SURFACE REMOVAL, 2"	SO YD	13,635	13,635			
44000100	PAVEMENT REMOVAL	SO YD	35,551	35,551			

CONSTRUCTION TYPE CODE: * = SPECIALTY ITEM
 (1) = SFTY 3N
 (2) = Y003
 (3) = Y005
 (4) = SFTY 2A

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 F.A.I. 80 & F.A.I. 55 INTERCHANGE
 SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: IMG
 DATE: JANUARY, 2005 CHECKED BY: MJL

DATE: 01/19/2005 FILENAME: N:\PROJ\2890\2890-02\Design\Misc\Sheets\S002890-S00-01.dgn