

CODE NO.	DESCRIPTION	UNIT	90% FED. 10% STATE		CONSTRUCTION TYPE CODE		
			TOTAL QTY	J000-2A	X20-2A FRONTAGE ROAD BRIDGE	Y030-1E	Y002-1C
* 73400100	CONCRETE FOUNDATIONS	CU YD	6				6
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	153.7				153.7
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	4				4
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3				3
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	2				2
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	12				12
73700200	REMOVE CONCRETE FOUNDATION-GROUND MOUNT	EACH	12				12
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	11				11
* 78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS	SQ FT	37	37			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44,347	44,347			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	9,883	9,883			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4,191	4,191			
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	31,425	31,275	150		
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	6,880	6,860	20		
78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	17,574	17,544	30		
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 12"	FOOT	135	115	20		
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37			
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	48,559	48,559			
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	7,153	7,153			
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	9,883	9,883			
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	4,191	4,191			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	402	402			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10		10		

CODE NO.	DESCRIPTION	UNIT	90% FED. 10% STATE		CONSTRUCTION TYPE CODE		
			TOTAL QTY	J000-2A	X20-2A FRONTAGE ROAD BRIDGE	Y030-1E	Y002-1C
* 78100300	REPLACEMENT REFLECTOR	EACH	1,352	1,352			
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	6		6		
* 78200400	GUARDRAIL REFLECTORS	EACH	15	15			
78300105	PAVEMENT MARKING REMOVAL	FOOT	134,378	134,378			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1	
* 80700140	GROUND ROD 5/8" DIA. X 10 FT.	EACH	164			164	
* 80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	27			27	
* 80800850	TEMPORARY WOOD POLE, 90 FT., CLASS 4, 15 FT. MAST ARM	EACH	14			14	
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	8			8	
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	8			8	
* 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16"x14"x6"	EACH	4			4	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	6			6	
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	40,000			40,000	
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1,800			1,800	
* 81701385	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350 MCM	FOOT	200			200	
* 81800700	AERIAL CABLE 3-1/C NO. 2 AWG ALUMINUM WITH MESSENGER WIRE	FOOT	13,500			13,500	
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	161			161	
* 82107110	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, SS HOUS.	EACH	8			8	
* 83050730	LIGHT POLE, ALUMINUM, 47-1/2 FT. M.H., 8 FT. DAVIT ARM	EACH	161			161	

CONSTRUCTION TYPE CODE: * = SPECIALTY ITEM
(1) = SFTY 3N
(2) = Y003
(3) = Y005
(4) = SFTY 2A

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
F.A.I. 80 & F.A.I. 55 INTERCHANGE

SUMMARY OF QUANTITIES

SCALE: N.T.S.
DATE: JANUARY, 2005

DRAWN BY: IMG
CHECKED BY: MJL

F.A.I. ROUTE SECTION COUNTY TOTAL SHEETS SHEET NO.
80-55 99-1(K,BY&AC-B) WILL 497 8

STA. TO STA.
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
CONTRACT NO. 80906