

DATE: 01/28/2005
FILENAME: N:\PROJ\226602890_02\Drawings\Misc\Sheets\SC022890_S00-07.dgn

CODE NO.	DESCRIPTION	UNIT	90% FED. 10% STATE		CONSTRUCTION TYPE CODE		
			TOTAL QTY	JO00-2A	X220-2A FRONTAGE ROAD BRIDGE	YO30-1E	YO02-1C
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42" HEIGHT	FOOT	317	317			
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DAY	411	411			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	56	56			
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	301.8				301.8
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	115				115
X7330115	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE B	FOOT	37				37
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	10			10	
X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING	EACH	38			38	
X8210190	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT (INSTALL ONLY)	EACH	14			14	
X8210302	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LUMINAIRES	L SUM	1			1	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	94,941	94,941			
Z0004600	BITUMINOUS DRIVEWAY PAVEMENT, 9"	SQ YD	76	76			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0014800	CULVERT TO BE CLEANED	FOOT	626	626			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2			
(1) Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6			
Z0064800	SELECTIVE CLEARING	UNIT	90	90			
A Z0076600	TRAINEES	HOUR	3000	3000			
XX004970	TEMPORARY PAVEMENT SUPERPAVE	SQ YD	1910	1910			
XX005272	CONDUIT PUSHED, 4" DIAMETER, RIGID GLAVANIZED STEEL	FOOT	150			150	
XX005449	AGGREGATE SUBGRADE 16"	SQ YD	14,563	14,563			
* X0324854	WEED CONTROL, NATIVE GRASS RESTORATION	GALLON	3.3	3.3			
X0324910	ACCIDENT REFERENCE MARKERS	EACH	118	118			

CODE NO.	DESCRIPTION	UNIT	90% FED. 10% STATE		CONSTRUCTION TYPE CODE		
			TOTAL QTY	JO00-2A	X220-2A FRONTAGE ROAD BRIDGE	YO30-1E	YO02-1C
X8202895	BITUMINOUS SHOULDERS SUPERPAVE 17"	SQ YD	30,848	30,848			
	3/4" PVC COATED FLEXIBLE LIQUID TIGHT METALLIC CONDUIT	FOOT	50			50	
X8110140	CONDUIT ATTACHED TO STRUCTURE, 3/4" RIGID GALVANIZED STEEL PVC COATED	FOOT	100			100	
X8110145	CONDUIT ATTACHED TO STRUCTURE, 1" RIGID GALVANIZED STEEL PVC COATED	FOOT	400			400	
X8110150	CONDUIT ATTACHED TO STRUCTURE, 3" RIGID GALVANIZED STEEL PVC COATED	FOOT	200			200	
X8110155	CONDUIT ATTACHED TO STRUCTURE, 4" RIGID GALVANIZED STEEL PVC COATED	FOOT	150			150	
X8100395	UNIT DUCT WITH 3-1/2" #2 & 1/2" #4 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA. SCH 40 POLY	FOOT	48,000			48,000	
X8100380	UNIT DUCT WITH 3-1/2" #2 & 1/2" #4 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIA. SCH 40 POLY	FOOT	1,000			1,000	
X8102010	CONDUIT PUSHED, 3" DIA. RIGID GALVANIZED STEEL	FOOT	1,800			1,800	
X8101280	CONDUIT IN TRENCH, 3" DIA. RIGID GALVANIZED STEEL	FOOT	1,300			1,300	
X8200800	REMOVAL OF POLE FOUNDATION ✓	EACH	31			31	
X0324915	RELOCATE LIGHTING UNITS AND POLES	EACH	1			1	
X0324917	REMOVAL OF EXISTING UNDERPASS FIXTURE, SALVAGE	EACH	16			16	
X8450100	REMOVAL OF EXISTING LIGHTING CONTROLLER, SALVAGE	EACH	1			1	
X0300525	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	3			3	
X0322191	REMOVAL OF TEMPORARY WOOD POLE	EACH	36			36	
X0321100	ROCK EXCAVATION FOR LIGHT POLE FOUNDATION	FOOT	400			400	
X8210025	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT, MULTI-TAP BALLAST	EACH	3			3	
X0324918	BUCK BOOST TRANSFORMER, 0.75kVA, 24V BOOST	EACH	2			2	

CONSTRUCTION TYPE CODE: * = SPECIALTY ITEM
 (1) = SFTY 3N
 (2) = Y003
 (3) = Y005
 (4) = SFTY 2A
 Δ = Y080

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 F.A.I. 80 & F.A.I. 55 INTERCHANGE
 SUMMARY OF QUANTITIES