

F.A.I. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80-55,99-1(K, BY&AC-B)	WILL		497	19
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 80906

DRAINAGE STRUCTURE SCHEDULE

LOCATION	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 (EACH)	INLET BOX STANDARD 542511 (TYPE C) (EACH)	CATCHBASINS TA, 4' DIA. T1 F OL (EACH)	CATCHBASINS TA, 4' DIA. T 3 F&G (EACH)	CATCHBASINS TA, 4' DIA. T8G (EACH)	CATCHBASINS TA, 4' DIA. T 20 F&G (EACH)	CATCHBASINS TA, 5' DIA. T1 F OL (EACH)	MANHOLES TA, 4' DIA. T1 F CL (EACH)	MANHOLES TA, 5' DIA. T1 F OL (EACH)	MANHOLES TA, 5' DIA. T1 F CL (EACH)	MANHOLES TA, 6' DIA. T1 F OL (EACH)	MANHOLES TA 6' DIA. T1 F CL (EACH)	MANHOLES TO BE ADJUSTED (EACH)	GRATES TYPE A (EACH)	DRAINAGE STRUCTURES 8'X3' W/2 T20 F&G (EACH)
FAI-80															
STA. 1951+32, 76' RT														1	
FAI-55															
STA. 1039+97, 3' RT		1													
STA. 1046+97	1														
STA. 1054+54															1
STA. 1055+96															1
STA. 1057+50			1												
STA. 1069+97	1														
STA. 1070+00, 58' LT									1						
RAMP A															
STA. 45+38, 18' LT						1									
STA. 45+39, 3' RT								1							
RAMP C															
STA. 14+04, 19' LT						1									
STA. 14+05, 3' RT															
STA. 14+05, 27' RT												1			
STA. 17+13, 17' RT												1			
STA. 19+00, 18' RT												1			
STA. 17+13, 14' LT							1								
STA. 21+60, 24' RT												1			
RAMP D															
STA. 16+84, 10' RT														1	
RAMP E															
STA. 14+02, 20' LT						1									
STA. 40+34, 20' LT						1									
RAMP G															
STA. 14+03, 3' RT															
STA. 14+04, 20' LT						1									
STA. 17+00, 24' LT							1								
STA. 35+75, 42' RT									1						
STA. 36+43, 22' RT													1		
STA. 36+81, 35' LT									1						
STA. 38+71, 16' LT														1	
STA. 38+41, 25' RT										1					
STA. 38+60, 7' RT				1											
STA. 39+92, 19' LT						1									
STA. 40+03, 16' RT														1	
STA. 40+13, 7' RT				1											
STA. 42+40, 7' RT				1											
STA. 42+50, 16' RT														1	
RAMP H															
STA. 3+59, 38' LT.						1									
TOTAL	2	1	1	3	1	6	2	3	3	1	4	3	1	2	2

DATE: 01/03/2005
 FILENAME: n:\proj\28902890_02\design\misc\schedule\schedule-08.dgn

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 F.A.I. 80 & F.A.I. 55 INTERCHANGE

SCHEDULE OF QUANTITIES

SCALE: N.T.S.
 DATE: JANUARY, 2005

DRAWN BY: IMG
 CHECKED BY: MJL