F.A.I. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80-55	99-10K,BY&AC-B)	WILL	497	20
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 80906

END SECTION SCHEDULE

LOCATION	PRC FLAR END SEC 12" (EACH)	PRC FLAR END SEC 18" (EACH)	PRC FLAR END SEC 24" (EACH)	PRC FLAR END SEC 30" (EACH)	PRC FLAR END SEC 42" (EACH)	PRC FLAR END S EL EQRS 24" (EACH)	PRC FLAR END S EL EOR 30" (EACH	CIP RC END SECTION 15" (EACH)	CIP RC END SECTION 18" (EACH)	CIP RC END SECTION 21" (EACH)	CIP RC END SECTION 24" (EACH)	CIP RC END SECTION 30" (EACH)	CIP RC END SECTION 36" (EACH)	METAL END SEC 12" (EACH)	GRT-C FLAR END SEC 24" (EACH	GRT-C FLAR END SEC 30" (EACH	GRT-C FLAR END SEC 42" (EACH)	GRT-C FL END S EOV 24" (CU. YD.)	GRT-C FL END S EOV 30" (CU. YD.)
FAI-80																			
STA. 1951+32, 135' RT														1					
FAI-55																			
STA. 1046+96, 78' LT			1												1				
STA. 1051+82, 86' LT	1																		
STA. 1052+29, 90' LT											1								
STA. 1055+19, 94' LT											1								
STA. 1055+53, 88' RT	1																		
STA. 1059+06			1												1				
STA. 1067+42, 77' LT						1												1	
STA. 1077+96, 77' LT		1																	
RAMP A																			
STA. 34+15, 88' LT										1									
STA. 35+17, 54' RT										1									
STA. 45+41, 42' RT														1					
RAMP B																			
STA. 12+90, 96' LT												1							
STA. 13+20, 59' RT				1												1			
RAMP C																			
STA. 13+03, 35' RT				1												1			
STA. 22+03, 27' LT		1																	
STA. 22+48, 90' LT							1												1
STA. 43+83, 27' RT				1												1			
STA. 43+83, 81' RT				1												1			
RAMP D																			
STA. 4+95, 52' RT			1												1				
STA. 5+09, 101' LT											1								
STA. 11+10, 121' RT					1												1		
STA. 11+23, 277' RT					1												1		
STA. 16+84, 67' RT														1					
RAMP E																			
STA. 14+02, 14' RT	1																		
STA. 21+02, 12' RT							1												1
STA. 22+11, 86' LT							1												1
STA. 35+27, 79' LT									1										
STA. 36+17, 40' RT									1										
STA. 40+34, 37' RT	1																		
STA. 42+63, 26' RT		1																	
RAMP F																			
STA. 12+33, 101' LT			1												1				
STA. 12+34, 31' RT											1								
RAMP G																			
STA. 14+03, 67' RT														1					
STA. 15+82, 67' RT			1												1				
STA. 17+00, 45' RT	1																		
STA. 21+46, 79' RT								1											
STA. 23+20, 98' LT								1											
STA. 33+10, 100' LT													1						
STA. 44+71, 20' RT					1												1		
RAMP H																			
STA. 4+80, 43' RT												1							
STA. 5+01, 118' LT												1							
STA. 16+50, 96' RT			1												1				
TOTAL	5	3	6	4	3	1	3	2	2	2	4	3	1	4	6	4	3	1	3

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
F.A.I. 80 & F.A.I. 55 INTERCHANGE

SCHEDULE OF QUANTITIES

SCALE: N.T.S.
DATE: JANUARY, 2005

DRAWN BY: IMG
CHECKED BY: MJL

DATE: 01/03/2005
FILENAME: n:\proj\2890\2890-02\design\misc\sheets\schedule\2890-schedule-07.dgn