F.A.I. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80-55	99-1(K,BY&AC-B)	WILL	497	24
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 80906

EARTHWORK SCHEDULE

LOCATION	STATION	PRE-STAGE							STAGE I							STAGE II						
		20200100	20200100	20201200	20400800		20200200	21101505	20200100	20200100	20201200	20400800		20200200	21101505	20200100	20200100	20201200	20400800		20200200	21101505
		EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)
RAMP G	17+00 TO 18+00	0	0	0	0	0	0	0	33	28	239	4,189	-4,161	0	257	0	0	0	0	0	0	0
	18+00 TO 19+00	0	0	0	0	0	0	0	33	28	211	4,409	-4,381	0	211	0	0	0	0	0	0	0
	19+00 TO 20+00	0	0	0	0	0	0	0	80	68	294	4,752	-4,684	0	215	0	0	0	0	0	0	0
	20+00 TO 21+00	0	0	0	0	0	0	0	63	54	178	4,752	-4,698	0	170	0	0	0	0	0	0	0
	21+00 TO 22+00	0	0	0	0	0	0	0	0	0	0	4,657	-4,657	0	119	0	0	0	0	0	0	0
	22+00 TO 23+00	0	0	0	0	0	0	0	0	0	0	4,357	-4,357	0	111	0	0	0	0	0	0	0
	23+00 TO 24+00	0	0	0	0	0	0	0	0	0	33	3,250	-3,250	0	128	0	0	0	0	0	0	0
	24+00 TO 25+00	0	0	0	0	0	0	0	0	0	35	2,293	-2,293	0	143	0	0	0	0	0	0	0
	25+00 TO 26+00	0	0	0	0	0	0	0	0	0	2	1,689	-1,689	0	98	0	0	0	0	0	0	0
	26+00 TO 27+00	0	0	0	0	0	0	0	0	0	0	1,087	-1,087	0	52	0	0	0	0	0	0	0
	27+00 TO 28+00	0	0	0	0	0	0	0	0	0	0	457	-457	0	50	0	0	0	0	0	0	0
	28+00 TO 29+00	0	0	0	0	0	0	0	91	77	407	72	5	0	87	0	0	0	0	0	0	0
	29+00 TO 30+00	0	0	0	0	0	0	0	367	312	1,069	0	312	0	169	0	0	0	0	0	0	0
	30+00 TO 31+00	0	0	0	0	0	0	0	1,374	1,168	1,504	0	1,168	0	235	0	0	0	0	0	0	0
	31+00 TO 32+00	0	0	0	0	0	0	0	2,193	1,864	1,578	0	1,864	0	239	0	0	0	0	0	0	0
	32+00 TO 33+00	0	0	0	0	0	0	0	1,948	1,656	1,376	0	1,656	0	202	0	0	0	0	0	0	0
	33+00 TO 34+00	0	0	0	0	0	0	0	1,494	1,270	1,165	0	1,270	0	165	0	0	0	0	0	0	0
	34+00 TO 35+00	0	0	0	0	0	0	0	1,146	974	1,022	0	974	0	150	0	0	0	0	0	0	0
	35+00 TO 36+00	0	0	0	0	0	0	0	998	848	974	0	848	0	152	0	0	0	0	0	0	0
	36+00 TO 37+00	0	0	0	0	0	0	0	676	575	661	181	393	0	122	0	0	0	0	0	0	0
	37+00 TO 38+00	0	0	0	0	0	0	0	209	178	361	185	-7	0	69	0	0	0	0	0	0	0
	TOTAL	0	0	0	0	0	0	0	10,706	9,100	11,109	36,331	-27,232	0	3,143	0	0	0	0	0	0	0
RAMP H	0+00 TO 1+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	393	334	1,091	0	334	0	229
	1+00 TO 2+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	558	474	1,335	3	471	0	279
	2+00 TO 3+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	643	547	1,413	118	429	0	297
	3+00 TO 4+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1,200	1,020	1,713	438	582	0	422
	4+00 TO 5+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2,543	2,161	1,706	232	1,929	0	374
	5+00 TO 6+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4,106	3,490	1,856	0	3,490	0	340
	6+00 TO 7+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3,228	2,744	1,255	0	2,744	0	236
	7+00 TO 8+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2,144	1,822	983	0	1,822	0	206
	8+00 TO 9+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1,709	1,453	763	113	1,339	0	202
	9+00 TO 10+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1,715	1,458	657	563	895	0	229
	10+00 TO 11+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2,283	1,940	888	771	1,169	0	257
	11+00 TO 12+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2,138	1,817	1,032	2,068	-251	0	341
	12+00 TO 13+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	567	482	527	3,035	-2,553	0	349
	13+00 TO 14+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	456	387	804	2,681	-2,294	0	364
	14+00 TO 15+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	275	234	795	1,675	-1,441	0	337
	15+00 TO 16+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	76	64	540	834	-770	0	331
	16+00 TO 17+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	214	182	474	430	-248	0	253
	17+00 TO 17+41	0	0	0	0	0	0	0	0	0	0	0	0	0	0	143	121	260	90	32	0	75
	H1 TO H2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	159	135	519	53	83	0	197
	TOTAL	0	0	0	0	0	0	0	0	0	0	0	0	0	0	24,549	20,866	18,612	13,105	7,762	0	5,318

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
F.A.I. 80 & F.A.I. 55 INTERCHANGE

SCHEDULE OF QUANTITIES

SCALE: N.T.S.
DATE: JANUARY, 2005

DRAWN BY: IMG
CHECKED BY: MJL

DATE: 01/03/2005
FILENAME: n:\proj\2890\2890-02\design\misc\sheets\schedule\2890-schedule-11.dgn