F.A.I. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80-55	99-1(K,BY&AC-B)	WILL	497	25
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 80906

EARTHWORK SCHEDULE

LOCATION	STATION	PRE-STAGE							STAGE I							STAGE II						
		20200100	20200100	20201200	20400800		20200200	21101505	20200100	20200100	20201200	20400800		20200200	21101505	20200100	20200100	20201200	20400800		20200200	21101505
		EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)
FAI 80 EB	1927+04 TO 1928+00	0	0	0	0	0	0	0	25	21	91	5	16	0	23	0	0	0	0	0	0	0
	1928+00 TO 1929+00	0	0	0	0	0	0	0	20	17	119	230	-212	0	74	0	0	0	0	0	0	0
	1929+00 TO 1930+00	0	0	0	0	0	0	0	19	16	113	489	-473	0	91	0	0	0	0	0	0	0
	1930+00 TO 1931+00	0	0	0	0	0	0	0	39	33	176	994	-961	0	93	0	0	0	0	0	0	0
	1931+00 TO 1931+55	0	0	0	0	0	0	0	26	22	137	742	-720	0	58	0	0	0	0	0	0	0
	1931+55 TO 1932+43	0	0	0	0	0	0	0	28	24	158	1,260	-1,236	0	78	0	0	0	0	0	0	0
	1932+43 TO 1933+00	0	0	0	0	0	0	0	18	15	72	1,029	-1,014	0	61	0	0	0	0	0	0	0
	1933+00 TO 1938+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	1938+00 TO 1939+00	0	0	0	0	0	0	0	272	231	480	806	-574	0	139	0	0	0	0	0	0	0
	1939+00 TO 1940+00	0	0	0	0	0	0	0	1,078	916	659	717	199	0	193	0	0	0	0	0	0	0
	1940+00 TO 1941+00	0	0	0	0	0	0	0	2,615	2,223	943	380	1,843	0	246	0	0	0	0	0	0	0
	1941+00 TO 1942+00	0	0	0	0	0	0	0	1,759	1,495	691	244	1,251	0	220	0	0	0	0	0	0	0
	1942+00 TO 1943+00	0	0	0	0	0	0	0	39	33	178	143	-110	0	91	0	0	0	0	0	0	0
	1956+00 TO 1957+00	0	0	0	0	0	0	0	1,257	1,069	506	0	1,069	0	115	0	0	0	0	0	0	0
	1957+00 TO 1958+00	0	0	0	0	0	0	0	1,587	1,349	937	2	1,347	0	176	0	0	0	0	0	0	0
	1958+00 TO 1959+00	0	0	0	0	0	0	0	420	357	919	4	354	0	202	0	0	0	0	0	0	0
	1959+00 TO 1960+00	0	0	0	0	0	0	0	163	139	709	2	137	0	189	0	0	0	0	0	0	0
	1960+00 TO 1961+00	0	0	0	0	0	0	0	176	150	622	0	150	0	115	0	0	0	0	0	0	0
	1961+00 TO 1962+00	0	0	0	0	0	0	0	167	142	415	0	142	0	59	0	0	0	0	0	0	0
	1965+00 TO 1966+00	0	0	0	0	0	0	0	120	102	396	41	62	0	48	0	0	0	0	0	0	0
	1966+00 TO 1967+00	0	0	0	0	0	0	0	41	35	287	48	-14	0	33	0	0	0	0	0	0	0
	1967+00 TO 1968+00	0	0	0	0	0	0	0	96	82	309	44	37	0	28	0	0	0	0	0	0	0
	1968+00 TO 1969+00	0	0	0	0	0	0	0	78	66	296	50	16	124	46	0	0	0	0	0	0	0
	1969+00 TO 1970+00	0	0	0	0	0	0	0	6	5	187	43	-38	389	67	0	0	0	0	0	0	0
	1970+00 TO 1971+00	0	0	0	0	0	0	0	6	5	348	37	-32	498	78	0	0	0	0	0	0	0
	1971+00 TO 1972+00	0	0	0	0	0	0	0	0	0	731	22	-22	689	72	0	0	0	0	0	0	0
	1972+00 TO 1973+00	0	0	0	0	0	0	0	15	13	504	113	-100	456	63	0	0	0	0	0	0	0
	1973+00 TO 1974+00	0	0	0	0	0	0	0	30	25	104	154	-129	0	61	0	0	0	0	0	0	0
	1974+00 TO 1975+00	0	0	0	0	0	0	0	28	24	100	44	-21	0	50	0	0	0	0	0	0	0
	1975+00 TO 1976+00	0	0	0	0	0	0	0	28	24	96	0	24	0	20	0	0	0	0	0	0	0
	1976+00 TO 1977+00	0	0	0	0	0	0	0	30	25	89	0	25	0	0	0	0	0	0	0	0	0
TOTAL		0	0	0	0	0	0	0	10,183	8,656	11,371	7,642	1,014	2,156	2,789	0	0	0	0	0	0	0

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
F.A.I. 80 & F.A.I. 55 INTERCHANGE

SCHEDULE OF QUANTITIES

SCALE: N.T.S.
DATE: JANUARY, 2005

DRAWN BY: IMG
CHECKED BY: MJL

DATE: 01/03/2005
FILENAME: n:\proj\2880\2880-02\design\miscsheets\schedule\2880-schedule-12.dgn