

EARTHWORK SCHEDULE

LOCATION	STATION	PRE-STAGE						STAGE I						STAGE II							
		20200100	20200100	20201200	20400800	20200200	2101505	20200100	20200100	20201200	20400800	20200200	2101505	20200100	20200100	20201200	20400800	20200200	2101505		
		EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)
FAI 55 NB	1026+13 TO 1027+00	19	16	76	0	16	0	13	0	0	0	0	0	0	0	0	0	0	0	0	0
	1027+00 TO 1028+00	19	16	76	0	16	0	13	0	0	0	0	0	0	0	0	0	0	0	0	0
	1028+00 TO 1029+00	19	16	78	0	16	0	9	0	0	0	0	0	0	0	0	0	0	0	0	0
	1029+00 TO 1030+53	31	26	125	0	26	0	11	23	19	60	0	19	0	0	0	0	0	0	0	0
	1030+53 TO 1031+00	10	8	35	0	8	0	2	17	15	43	0	15	0	0	0	0	0	0	0	0
	1031+00 TO 1031+23	5	4	17	0	4	0	1	10	8	27	3	5	0	1	0	0	0	0	0	0
	1031+23 TO 1032+00	13	11	56	0	11	0	6	33	28	106	23	5	0	0	0	0	0	0	0	0
	1032+00 TO 1033+00	19	16	72	0	16	0	6	46	39	156	44	-5	0	0	0	0	0	0	0	0
	1033+00 TO 1034+00	19	16	70	0	16	0	6	46	39	180	54	-14	0	4	0	0	0	0	0	0
	1034+00 TO 1034+54	9	8	35	0	8	0	4	13	11	103	26	-13	0	3	0	0	0	0	0	0
	1034+54 TO 1035+00	13	11	29	1	10	0	4	6	5	83	24	-19	0	6	0	0	0	0	0	0
	1035+00 TO 1036+00	30	25	63	2	23	0	13	24	20	174	69	-48	0	24	0	0	0	0	0	0
	1036+00 TO 1037+00	19	16	63	4	12	0	11	30	25	187	89	-64	0	28	0	0	0	0	0	0
	1037+00 TO 1038+00	17	14	63	9	5	0	11	30	25	144	50	-25	0	22	0	0	0	0	0	0
	1038+00 TO 1039+00	20	17	61	9	8	0	15	26	22	93	0	22	0	15	0	0	0	0	0	0
	1039+00 TO 1040+00	31	27	56	4	23	0	15	26	22	93	0	22	0	15	0	0	0	0	0	0
	1040+00 TO 1041+00	37	31	56	0	31	0	15	26	22	93	0	22	0	15	0	0	0	0	0	0
	1041+00 TO 1042+00	24	20	61	6	15	0	15	28	24	93	0	24	0	15	0	0	0	0	0	0
	1042+00 TO 1043+00	17	14	63	11	3	0	15	33	28	137	0	28	0	20	0	0	0	0	0	0
	1043+00 TO 1044+00	24	20	59	6	15	0	15	26	22	239	120	-98	0	65	0	0	0	0	0	0
	1044+00 TO 1045+00	52	44	113	0	44	0	19	156	132	504	120	12	0	139	0	0	0	0	0	0
	1045+00 TO 1046+00	46	39	122	15	25	0	39	20	656	557	0	557	0	209	0	0	0	0	0	0
	1046+00 TO 1047+00	22	19	61	15	4	0	17	524	445	689	298	147	0	207	0	0	0	0	0	0
	1047+00 TO 1048+00	37	31	81	0	31	0	15	35	30	91	361	-331	0	144	0	0	0	0	0	0
	1048+00 TO 1049+00	41	35	111	0	35	0	13	37	31	93	78	-46	0	70	0	0	0	0	0	0
	1049+00 TO 1050+00	35	30	100	0	30	0	9	57	49	128	28	21	0	15	0	0	0	0	0	0
	1050+00 TO 1051+00	30	25	78	13	12	0	7	74	63	157	13	50	0	7	0	0	0	0	0	0
	1051+00 TO 1052+00	30	25	74	13	12	0	6	61	52	94	0	52	0	6	0	0	0	0	0	0
	1052+00 TO 1053+00	37	31	85	0	31	0	2	54	46	70	0	46	0	2	0	0	0	0	0	0
	1053+00 TO 1054+00	37	31	85	0	31	0	0	69	58	41	0	58	0	0	0	0	0	0	0	0
	1054+00 TO 1055+00	39	33	72	0	33	0	0	72	58	39	0	58	0	2	0	0	0	0	0	0
	1055+00 TO 1056+00	31	27	59	37	-10	0	0	50	43	44	0	43	0	4	0	0	0	0	0	0
	1056+00 TO 1057+00	24	20	59	61	-41	0	4	43	36	31	0	36	0	4	0	0	0	0	0	0
	1057+00 TO 1058+00	22	19	57	39	-20	0	7	115	98	131	0	98	0	2	0	0	0	0	0	0
	1058+00 TO 1059+00	22	19	54	15	4	0	9	113	96	163	7	89	0	0	0	0	0	0	0	0
	1059+00 TO 1060+00	24	20	46	11	9	0	13	46	33	78	313	-285	0	37	0	0	0	0	0	0
	1060+00 TO 1061+00	22	19	39	19	0	0	15	30	25	70	941	-916	0	124	0	0	0	0	0	0
	1061+00 TO 1062+00	22	19	39	41	-22	0	13	537	456	524	659	-203	0	187	0	0	0	0	0	0
	1062+00 TO 1063+00	22	19	41	46	-27	0	11	906	770	744	57	712	0	167	0	0	0	0	0	0
	1063+00 TO 1064+00	22	19	43	28	-9	0	13	578	491	378	76	415	0	109	0	0	0	0	0	0
	1064+00 TO 1065+00	20	17	43	26	-9	0	15	224	190	176	74	116	0	65	0	0	0	0	0	0
	1065+00 TO 1066+00	19	16	50	17	-1	0	15	122	104	202	52	52	0	54	0	0	0	0	0	0
	1066+00 TO 1067+00	20	17	52	11	6	0	15	198	168	387	31	137	0	50	0	0	0	0	0	0
	1067+00 TO 1068+00	39	33	85	6	28	0	15	207	176	376	76	100	0	39	0	0	0	0	0	0
	1068+00 TO 1069+00	39	33	91	6	28	0	15	202	172	254	154	18	0	41	0	0	0	0	0	0
	1069+00 TO 1070+00	20	17	52	15	3	0	15	191	162	237	209	-47	0	44	0	0	0	0	0	0
	1070+00 TO 1071+00	20	17	46	13	4	0	15	172	146	237	224	-78	0	48	0	0	0	0	0	0
	1071+00 TO 1072+00	22	19	46	11	8	0	15	143	121	235	193	-71	0	44	0	0	0	0	0	0
	1072+00 TO 1073+00	26	22	57	11	11	0	15	109	93	239	161	-68	0	39	0	0	0	0	0	0
	1073+00 TO 1074+00	28	24	52	11	13	0	13	83	71	259	109	-38	0	41	0	0	0	0	0	0
	1074+00 TO 1075+00	24	20	41	7	13	0	13	57	49	257	98	-49	0	41	0	0	0	0	0	0
	1075+00 TO 1076+00	20	17	46	2	15	0	15	43	36	241	98	-62	0	35	0	0	0	0	0	0
	1076+00 TO 1077+00	22	19	52	2	17	0	15	37	31	233	83	-52	0	35	0	0	0	0	0	0
	1077+00 TO 1078+00	26	22	57	0	22	0	15	57	33	178	78	-49	0	31	0	0	0	0	0	0
	1078+00 TO 1079+00	26	22	65	0	22	0	15	33	28	131	56	-27	0	24	0	0	0	0	0	0
	1079+00 TO 1080+00	24	20	63	0	20	0	15	35	30	141	39	-9	0	22	0	0	0	0	0	0
	1080+00 TO 1081+00	20	17	56	0	17	0	15	35	30	139	30	0	0	20	0	0	0	0	0	0
	1081+00 TO 1082+00	19	16	57	0	16	0	15	35	30	135	26	4	0	19	0	0	0	0	0	0
	1082+00 TO 1083+00	22	19	56	0	19	0	13	56	37	143	20	11	0	17	0	0	0	0	0	0
	1083+00 TO 1084+00	24	20	52	0	20	0	13	39	33	141	19	15	0	15	0	0	0	0	0	0
	1084+00 TO 1084+94	21	18	49	0	18	0	14	38	33	145	9	24	0	16	0	0	0	0	0	0
	TOTAL	1,513	1,286	3,800	540	746	0	1,286	6,712	5,705	11,587	5,292	414	0	2,412	0	0	0	0	0	0

DATE: 01/03/2005
 FILENAME: \\j:\proj\2005\80906-02\design\msh\sheet\schedule\2890-schedule_14.dgn

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 F.A.I. 80 & F.A.I. 55 INTERCHANGE

SCHEDULE OF QUANTITIES

SCALE: N.T.S.
 DATE: JANUARY, 2005

DRAWN BY: IMG
 CHECKED BY: MJL