

EARTHWORK SCHEDULE

LOCATION	STATION	PRE-STAGE						STAGE I						STAGE II								
		20200100	20200100	20201200	20400800	20200200	21101505	20200100	20200100	20201200	20400800	20200200	21101505	20200100	20200100	20201200	20400800	20200200	21101505			
		EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EARTH EXCAVATION (CU YD)	EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	ROCK EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)
FAL 55 SB	1024+26 TO 1025+00	0	0	67	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	1025+00 TO 1026+00	0	0	93	0	0	0	0	4	93	0	0	0	0	0	0	0	0	0	0	0	0
	1026+00 TO 1027+00	0	0	89	0	0	0	0	7	11	9	130	7	2	0	33	0	0	0	0	0	0
	1027+00 TO 1028+00	0	0	93	0	0	0	0	7	0	0	137	0	0	0	26	0	0	0	0	0	0
	1028+00 TO 1029+00	0	0	93	0	0	0	0	7	11	9	157	0	9	0	26	0	0	0	0	0	0
	1029+00 TO 1030+00	7	6	78	9	-3	0	9	44	38	206	33	4	0	26	0	0	0	0	0	0	0
	1030+00 TO 1031+00	15	13	65	17	-4	0	11	76	65	257	65	0	0	26	0	0	0	0	0	0	0
	1031+00 TO 1032+00	15	13	63	11	1	0	11	72	61	267	65	-3	0	28	0	0	0	0	0	0	0
	1032+00 TO 1033+00	15	13	65	4	9	0	9	43	36	191	46	-10	0	15	0	0	0	0	0	0	0
	1033+00 TO 1034+00	15	13	69	0	13	0	11	28	24	131	28	-4	0	13	0	0	0	0	0	0	0
	1034+00 TO 1035+00	15	13	69	0	13	0	11	28	24	137	33	-10	0	20	0	0	0	0	0	0	0
	1035+00 TO 1036+00	15	13	67	0	13	0	4	30	25	169	19	7	0	19	0	0	0	0	0	0	0
	1036+00 TO 1037+00	15	13	67	0	13	0	0	44	38	196	0	38	0	11	0	0	0	0	0	0	0
	1037+00 TO 1038+00	15	13	69	0	13	0	6	61	52	220	11	41	0	15	0	0	0	0	0	0	0
	1038+00 TO 1039+00	15	13	70	0	13	0	11	52	44	180	11	33	0	15	0	0	0	0	0	0	0
	1039+00 TO 1040+00	17	14	70	0	14	0	9	37	31	107	0	31	0	4	0	0	0	0	0	0	0
	1040+00 TO 1041+00	17	14	69	0	14	0	4	37	31	107	0	31	0	4	0	0	0	0	0	0	0
	1041+00 TO 1042+00	17	14	67	0	14	0	2	44	38	213	0	38	0	24	0	0	0	0	0	0	0
	1042+00 TO 1043+00	19	16	67	0	16	0	6	407	346	507	0	346	0	76	0	0	0	0	0	0	0
	1043+00 TO 1044+00	19	16	67	0	16	0	9	931	792	770	0	792	0	131	0	0	0	0	0	0	0
	1044+00 TO 1045+00	39	33	94	0	33	0	13	724	615	856	19	597	0	176	0	0	0	0	0	0	0
	1045+00 TO 1046+00	37	31	98	6	26	0	15	369	313	678	570	-257	0	219	0	0	0	0	0	0	0
	1046+00 TO 1047+00	15	13	63	20	-8	0	15	213	181	259	559	-378	0	124	0	0	0	0	0	0	0
	1047+00 TO 1048+00	31	27	87	15	12	0	13	39	33	46	7	26	0	9	0	0	0	0	0	0	0
	1048+00 TO 1049+00	48	41	130	0	41	0	9	43	36	69	0	36	0	9	0	0	0	0	0	0	0
	1049+00 TO 1050+00	46	39	131	0	39	0	7	48	41	117	9	32	0	11	0	0	0	0	0	0	0
	1050+00 TO 1051+00	37	31	104	0	31	0	7	52	44	98	9	35	0	15	0	0	0	0	0	0	0
	1051+00 TO 1052+00	30	25	89	0	25	0	7	65	55	41	2	53	0	13	0	0	0	0	0	0	0
	1052+00 TO 1053+00	31	27	96	0	27	0	7	72	61	48	2	60	0	6	0	0	0	0	0	0	0
	1053+00 TO 1054+00	33	28	94	0	28	0	4	56	47	57	0	47	0	0	0	0	0	0	0	0	0
	1054+00 TO 1055+00	33	28	93	0	28	0	0	61	52	61	31	20	0	9	0	0	0	0	0	0	0
	1055+00 TO 1056+00	26	22	74	28	-6	0	0	57	49	98	57	-9	0	26	0	0	0	0	0	0	0
	1056+00 TO 1057+00	17	14	59	54	-40	0	4	39	33	187	26	7	0	52	0	0	0	0	0	0	0
	1057+00 TO 1058+00	19	16	63	54	-38	0	7	37	31	148	217	-185	0	46	0	0	0	0	0	0	0
	1058+00 TO 1059+00	22	19	59	57	-39	0	7	33	28	50	293	-264	0	31	0	0	0	0	0	0	0
	1059+00 TO 1060+00	19	16	50	54	-38	0	9	57	49	317	156	-107	0	98	0	0	0	0	0	0	0
	1060+00 TO 1061+00	19	16	43	43	-27	0	11	441	375	870	169	206	0	198	0	0	0	0	0	0	0
	1061+00 TO 1062+00	20	17	41	61	-44	0	11	41	689	586	172	413	0	204	0	0	0	0	0	0	0
	1062+00 TO 1063+00	20	17	50	43	-25	0	11	404	343	456	141	202	0	126	0	0	0	0	0	0	0
	1063+00 TO 1064+00	20	17	50	20	-3	0	13	133	113	150	57	56	0	43	0	0	0	0	0	0	0
	1064+00 TO 1065+00	20	17	43	22	-5	0	15	43	37	31	35	0	31	0	24	0	0	0	0	0	0
	1065+00 TO 1066+00	22	19	44	6	13	0	15	37	31	24	0	31	0	35	0	0	0	0	0	0	0
	1066+00 TO 1067+00	22	19	44	6	13	0	15	37	31	9	0	31	0	19	0	0	0	0	0	0	0
	1067+00 TO 1068+00	41	35	80	2	33	0	15	39	33	31	4	29	0	20	0	0	0	0	0	0	0
	1068+00 TO 1069+00	41	35	87	4	31	0	15	41	35	46	4	31	0	19	0	0	0	0	0	0	0
	1069+00 TO 1070+00	22	19	52	15	4	0	15	52	47	169	17	31	0	37	0	0	0	0	0	0	0
	1070+00 TO 1071+00	22	19	46	17	2	0	15	65	55	244	43	13	0	50	0	0	0	0	0	0	0
	1071+00 TO 1072+00	20	17	46	13	4	0	15	46	49	156	54	-5	0	31	0	0	0	0	0	0	0
	1072+00 TO 1073+00	30	25	78	7	18	0	15	59	50	148	50	0	0	26	0	0	0	0	0	0	0
	1073+00 TO 1074+00	31	27	78	11	16	0	13	61	52	180	41	11	0	28	0	0	0	0	0	0	0
	1074+00 TO 1075+00	24	20	46	15	6	0	13	46	39	196	31	8	0	30	0	0	0	0	0	0	0
	1075+00 TO 1076+00	24	20	48	9	11	0	15	33	28	198	26	2	0	26	0	0	0	0	0	0	0
	1076+00 TO 1077+00	22	19	54	6	13	0	15	33	28	176	28	1	0	22	0	0	0	0	0	0	0
	1077+00 TO 1078+00	24	20	56	2	19	0	15	30	25	148	33	-8	0	20	0	0	0	0	0	0	0
	1078+00 TO 1079+00	24	20	52	2	19	0	15	30	25	137	26	-1	0	19	0	0	0	0	0	0	0
	1079+00 TO 1080+00	22	19	54	17	2	0	15	31	27	143	19	8	0	19	0	0	0	0	0	0	0
	1080+00 TO 1081+00	24	20	56	2	19	0	15	33	28	148	20	8	0	19	0	0	0	0	0	0	0
	1081+00 TO 1082+00	26	22	57	0	22	0	15	35	30	150	17	13	0	19	0	0	0	0	0	0	0
	1082+00 TO 1083+00	26	22	57	0	22	0	15	33	28	150	17	12	0	19	0	0	0	0	0	0	0
	1083+00 TO 1084+00	24	20	44	0	20	0	15	37	31	144	22	9	0	22	0	0	0	0	0	0	0
	1084+00 TO 1084+94	23	19	40	0	19	0	14	31	27	82	40	-13	0	30	0	0	0	0	0	0	0
	TOTAL	1,326	1,127	4,183	633	494	0	618	6,463	5,493	12,363	3,312	2,181	0	2,476	0	0	0	0	0	0	0

DATE: 01/03/2005
 FILENAME: r:\03\28902890-02\design\msh\schedule\2890-schedule-15.dgn

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 F.A.I. 80 & F.A.I. 55 INTERCHANGE
 SCHEDULE OF QUANTITIES
 SCALE: N.T.S. DRAWN BY: IMG
 DATE: JANUARY, 2005 CHECKED BY: MJL