F.A.I. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80-55	99-1(K,BY&AC-B)	WILL	497	29
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 80906

EARTHWORK SCHEDULE

LOCATION	STATION	PRE-STAGE 20200100 EARTH EXCAVATION (CU YD)	PRE-STAGE 20200100 EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	PRE-STAGE 20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	PRE-STAGE 20400800 FURNISHED EXCAVATION (CU YD)	PRE-STAGE EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	PRE-STAGE 20200200 ROCK EXCAVATION (CU YD)	PRE-STAGE 21101505 TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	STAGE I 20200100 EARTH EXCAVATION (CU YD)	STAGE I 20200100 EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	STAGE I 20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	STAGE I 20400800 FURNISHED EXCAVATION (CU YD)	STAGE I EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	STAGE I 20200200 ROCK EXCAVATION (CU YD)	STAGE I 21101505 TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	STAGE II 20200100 EARTH EXCAVATION (CU YD)	STAGE II 20200100 EARTH-EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	STAGE II 20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	STAGE II 20400800 FURNISHED EXCAVATION (CU YD)	STAGE II EATHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)	STAGE II 20200200 ROCK EXCAVATION (CU YD)	STAGE II 21101505 TOPSOIL EXCAVATION AND PLACEMENT (CU YD)
W. FRONTAGE ROAD	42+75 TO 43+00	0	0	0	0	0	0	0	4	3	51	0	3	0	0	0	0	0	0	0	0	0
	43+00 TO 44+00	0	0	0	0	0	0	0	39	33	202	0	33	0	0	0	0	0	0	0	0	0
	44+00 TO 45+00	0	0	0	0	0	0	0	43	36	187	0	36	0	0	0	0	0	0	0	0	0
	45+00 TO 46+00	0	0	0	0	0	0	0	20	17	170	0	17	0	0	0	0	0	0	0	0	0
	46+00 TO 47+00	0	0	0	0	0	0	0	31	27	189	0	27	0	0	0	0	0	0	0	0	0
	47+00 TO 48+00	0	0	0	0	0	0	0	31	27	207	0	27	0	0	0	0	0	0	0	0	0
	TOTAL	0	0	0	0	0	0	0	169	143	1,006	0	143	0	0	0	0	0	0	0	0	0
	TOTALS	2,839	2,413	7,983	1,173	1,240	0	1,311	84,295	71,650	84,717	150,193	-78,543	3,781	25,249	89,200	75,820	59,775	81,147	-5,327	0	19,917
ADDITIONAL UNDERCUTS		-	-	-	-	-	-	-	-	-	2,465	-	-	-	-	-	-	1,035	-	-	-	-
ADDITIONAL WORK FOR TEMP RAMPS		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	120	2,778	-	-	-
PAY ITEM TOTALS		-	2,413	7,983	0	-	0	1,311	-	71,650	87,182	78,543	-	3,781	25,249	-	75,820	60,930	8,105	-	0	19,917

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
F.A.I. 80 & F.A.I. 55 INTERCHANGE

SCHEDULE OF QUANTITIES

SCALE: N.T.S.
DATE: JANUARY, 2005

DRAWN BY: IMG
CHECKED BY: MJL

DATE: 01/03/2005
FILENAME: n:\proj\2890\2890-C2\design\misc-sheets\schedule\2890-schedule-15.dgn