

SUMMARY OF QUANTITIES - SIGNING CONTRACT SIGN WORK

CODED PAY ITEM	PAY ITEM	SIGN NO.	SIGN PANEL, TY 3 AND STRUCTURES		SIGN PANEL ASSEMBLY TYPE A AND TYPE B REMOVAL		SIGN PANEL ASSEMBLY TYPE 2 AND TYPE 3 INSTALLATION	
			UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL
72000200	SIGN PANEL - TYPE 2		SQ FT	129.1			129.1	
72000300	SIGN PANEL - TYPE 3		SQ FT	5421.1	5421.1			
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A		EACH	62		62		
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B		EACH	25	8	17		
72400330	REMOVE SIGN PANEL-TYPE 3		SQ FT	1685.0	1685.0			
73000100	WOOD SIGN SUPPORT		FOOT	441.3	288.0		153.3	
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4'-6")		FOOT	560.0	560.0			
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" x 7'-0")		FOOT	199.0	199.0			
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED		FOOT	37.0	37.0			
73400100	CONCRETE FOUNDATIONS		CU YD	6.0	6.0			
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS		CU YD	153.7	153.7			
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	4	4			
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER		EACH	3	3			
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED		EACH	2	2			
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT		EACH	12	12			
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT		EACH	12	12			
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD		EACH	11	11			
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A		FOOT	301.8	301.8			
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A		FOOT	115.0	115.0			
X7330115	OVERHEAD SIGN STRUCTURE WALKWAY, BRIDGE MOUNTED		FOOT	37.0	37.0			
X8210055	FLUORESCENT LUMINAIRE FOR SIGN LIGHTING		EACH	38	38			

SUMMARY OF QUANTITIES - SIGNING FOR INFORMATION ONLY

CODED PAY ITEM	PAY ITEM	SIGN NO.	1C099I055R249.4		1C099I055R250.7		MP 250.70	
			UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL
72000300	SIGN PANEL - TYPE 3		SQ FT	377.0	188.5	188.5		
72400330	REMOVE SIGN PANEL-TYPE 3		SQ FT	188.5			188.5	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKWAY		POUND	836.0	836.0			
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" x 7'-0")		FOOT	32.0		32.0		
73400100	CONCRETE FOUNDATIONS		CU YD	2.4	2.4			
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS		CU YD	8.9		8.9		
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT		EACH	2.0			2.0	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD		EACH	2.0			2.0	
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A		FOOT	15.5		15.5		


SGN-01

REVISIONS	
NAME	DATE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
F.A.I. 80 & F.A.I. 55 INTERCHANGE

SUMMARY OF QUANTITY
SIGNING

SCALE: NONE
DATE: JANUARY, 2004
DRAWN BY: RV
DESIGNED BY: AS
CHECKED BY: MSA



nt:\pro\28990\28990-02\design\signing\sign-01.dgn 1/31/2005