

CONTRACT NO. 86603

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
80	*	LASALLE	460	5

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

* (50-2)HBR, (7)XIN&TS-1

← ACF →

SUMMARY OF QUANTITIES				URBAN		CONSTRUCTION TYPE CODE			90% FED 10% STATE		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000-2A ROADWAY IL 351	J000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY IL 351	I000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J000-2A I-80	X771-2A EXIST S.N. 050-0026 PROP. SN 050-0230 I-80
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	1199		1199						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1								1
50102400	CONCRETE REMOVAL	CU YD	4							4	
50104400	CONCRETE HEADWALL REMOVAL	EACH	21	4						17	
50105220	PIPE CULVERT REMOVAL	FOOT	999	709						290	
50200100	STRUCTURE EXCAVATION	CU YD	535.8								535.8
50300225	CONCRETE STRUCTURES	CU YD	457.8								457.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	485.2							6	479.2
50300260	BRIDGE DECK GROOVING	SQ YD	1221.3								1221.3
50300300	PROTECTIVE COAT	SQ YD	1662.7								1662.7
50500305	ERECTING STRUCTURAL STEEL	L SUM	1								1
50500505	STUD SHEAR CONNECTORS	EACH	6016								6016
50800105	REINFORCEMENT BARS	POUND	660							660	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	188300							5780	182520
51100100	SLOPE WALL 4 INCH	SQ YD	272.5								272.5
51201600	FURNISHING STEEL PILES HP12X53	FOOT	3690								3690
51202700	DRIVING STEEL PILES	FOOT	3690								3690
51203600	TEST PILE STEEL HP12X53	EACH	3								3
51205200	TEMPORARY SHEET PILING	SQ FT	341.6								341.6
51500100	NAME PLATES	EACH	1								1
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	171							171	
54201285	PIPE CULVERTS, TYPE 2 RCCP 30"	FOOT	73							73	
54201291	PIPE CULVERTS, TYPE 2 RCCP 36"	FOOT	20							20	
54213447	END SECTIONS 12"	EACH	3							3	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	14	9						5	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	7	6						1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	8	6						2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	3						4	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2							2	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	1						2	
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2							
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2							2	

← ACIM →

* INDICATES SPECIALTY ITEM

11/1/2004 c:\pro\jects\ec02991\cvs\stf.dgn

SUMMARY