F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X)N & TS-1	LASALLE	460	2H
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE: I 000-1A ROADWAY	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY	MAIN 2A STATE ENTRANCE 100% STATE	Y030-1E LIGHTING 100% CITY	I000 BITUMINOUS	J000 CONCRETE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETERS)	UNIT	47	47					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	55	55					
20100500	TREE REMOVAL, ACRES	ACRE	0.2	0.2					
10101000	TEMPORARY FENCE	FOOT	60	60					
10101200	TREE ROOT PRUNING	EACH	10	10					
2[illegible]2001[illegible]	EARTH EXCAVATION	CU YD	4569	4569					
2[illegible]00[illegible]0	TRENCH BACKFILL	CU YD	432	432					
2[illegible]01[illegible]5	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10,589	10,589					
21[illegible]0[illegible]10	EXPLORATION TRENCH SPECIAL	FOOT	100	100					
250[illegible]210	SEEDING, CLASS 1A	ACRES	4.1	4.1					
2500[illegible]400	NITROGEN FERTILIZER NUTRIENT	POUND	369	369					
250[illegible]500	PHOSHORUS FERTILIZER NUTRIENT	POUND	369	369					
250[illegible]600	POTASSIUM FERTILIZER NUTRIENT	POUND	369	369					
29[illegible]5	MULCH, METHOD 2	ACRE	4.1	4.1					
2[illegible]002[illegible]0	TEMPORARY EROSION CONTROL SEEDING	POUND	1,230	1,230					
2[illegible]0003[illegible]	TEMPORARY DITCH CHECKS	EACH	40	40					
[illegible]00050	INLET AND PIPE PROTECTION	EACH	33	33					
[illegible]1100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	9267.0				9267.0		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	9275.0					9275.0	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	465	465					
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	1,430.0				1,430.0		
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	470.0					470.0	

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = $FILE$
PLOT SCALE = $PLOTSCALE$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | STRUCTURE DETAIL | DRAWN | CHECKED | BY | DATE

NOTE BOOK NO.

REVISIONS	
NAME	DATE

SCHEDULE

ILLINOIS DEPARTMENT OF TRANSPORTATION

~~SUMMARY~~ OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
1011 SOUTH 6TH STREET
SPRINGFIELD, ILLINOIS 62703
PROFESSIONAL DESIGN FIRM NO. 184-000115
(PROFESSIONAL ENGINEERING CORPORATION)
(217) 753-5864, (217) 753-5370 (FAX), E-MAIL: "mail@greenebradford.com"

COMPUTER FILE NO. SUMMARY 01
PROJECT 01194_B_N
08/29/04-GSJ