

DESIGN		
INT. DATE	REASON	

PLOTS & CHECKS		
INT. DATE	NO.	REASON

FILE NAME = \$FILES\$
 PLOT SCALE = \$PLOTSCALE\$
 PLOT DATE = \$DATE\$
 PLOT TIME = \$TIME\$
 OPERATOR = \$OPERATOR\$

PROFILE NO. _____
 DATE _____

NO. _____

CHECKS		
INT. DATE	REASON	

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70XN & TS-1)	LASALLE	460	236
STA. _____		TO STA. _____		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 86603				

EROSION CONTROL SCHEDULE		
LOCATION	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION
	EACH	EACH
IL. RTE. 351		
STA. 248+03, 32.6' LT		1
STA. 247+99, 33' RT.	1	
STA. 248+11, 33' LT.	1	
STA. 249+23, 34.41' LT		1
STA. 249+95, 32' LT.	1	
STA. 250+87, 32.42' LT		1
STA. 251+95, 42' LT.	1	
STA. 252+16, 45' LT		1
STA. 252+69, 46' LT.	1	
STA. 252+75, 45' LT.		1
STA. 254+00, 45' LT.		1
STA. 254+30, 45' LT.		1
STA. 254+80, 45' LT.		1
STA. 255+37, 46' LT.	1	
STA. 255+42, 45' LT.		1
STA. 256+14, 45' LT.		1
STA. 256+68, 45' LT.	1	
STA. 256+75, 45' LT.		1
STA. 256+83, 45.17' LT.	1	
STA. 257+25, 26.5' RT		1
STA. 257+68, 45' LT.	1	
STA. 257+75, 45' LT.		1
STA. 257+82, 45' LT.	1	
STA. 258+05, 45' LT.		1
STA. 258+62, 45' LT.		1
STA. 259+14, 45' LT.		1
STA. 259+93, 44' LT.	1	
STA. 260+00, 45' LT.		1
STA. 260+06, 44' LT.	1	
STA. 260+50, 26.5' RT		1
STA. 261+25, 45' LT.		1
STA. 261+25, 29' RT.		1
STA. 261+53, 61' LT.	1	
STA. 261+60, 63' LT.		1
STA. 261+60, 50' RT.		1
STA. 261+68, 67' LT.	1	
STA. 263+39, 47' LT.	1	
STA. 263+46 45' LT.		1
STA. 263+52, 47' RT.	1	
STA. 263+54, 47' LT.	1	
STA. 48+52, 56' RT.	1	
STA. 48+52, 53' LT.	1	
STA. 50+52, 55' LT.	1	
STA. 50+52, 50' LT.	1	
STA. 52+53, 57' RT.	1	
STA. 52+55, 50' LT.	1	
CIVIC ROAD		
STA. 44+60, 28.31' LT.		1
STA. 45+32, 29' LT.	1	
STA. 45+51, 31' RT.	1	
STA. 45+55, 34' RT.		1
STA. 46+20, 30' LT.	1	
STA. 46+24, 31.2' LT.		1
STA. 47+00, 30' LT.	1	
STA. 47+01, 32' RT.	1	
STA. 48+72, 34' LT.	1	
STA. 48+74, 32' RT.	1	

EROSION CONTROL SCHEDULE		
LOCATION	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION
	EACH	EACH
NORTH 30TH ROAD		
STA. 50+91.81, 42.38' RT.		1
STA. 51+02, 33' LT.	1	
STA. 51+04.61, 28.90' LT.		1
STA. 51+05.07, 34.27' RT.		1
STA. 51+10, 34' RT.	1	
STA. 51+94, 32' RT.	1	
STA. 52+00, 33' RT.		1
STA. 53+01, 32' RT.	1	
STA. 54+04, 31' RT.	1	
STA. 54+36, 21' LT.		1
STA. 54+36, 31.5' RT.		1
STA. 55+01, 31' RT.	1	
STA. 55+50, 31' RT.	1	
STA. 56+00, 32' RT.		1
STA. 56+04, 31' RT.	1	
STA. 56+67, 30' RT.	1	
STA. 58+40, 30' RT.	1	
TOTALS	40	33

UTILITIES TO BE ADJUSTED SCHEDULE				
LOCATION	WATER VALVE TO BE ADJUSTED	WATER VALVE TO BE MOVED	FIRE HYDRANT TO BE MOVED	DOMESTIC METER VAULTS TO BE ADJUSTED
	EACH	EACH	EACH	EACH
IL RTE 351				
STA. 259+91, 38' LT.				1
STA. 255+40, 45' LT.		1	1	
STA. 261+40, 18' LT.	1			
CIVIC ROAD				
STA. 44+30, 42' LT.			1	
STA. 44+32, 36' LT.		1		
STA. 44+33, 41' LT.		1		
STA. 44+36, 38' LT.		1		
STA. 48+60, 31' RT.		1		
STA. 48+60, 28' RT.			1	
N. 30TH ROAD				
STA. 51+72, 27' LT.			1	
STA. 51+72, 25' LT.		1		
STA. 51+75, 23' LT.		1		
TOTALS	1	7	4	1

EARTHWORK							
LOCATION	EARTH EXCAVATION (C)	EARTH EXCAVATION (WIDENING) (C)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (F)	EMBANKMENT (WIDENING) (F)	EARTHWORK BALANCE WASTE (+) OR SHRINKAGE (-)	TOPSOIL FURNISH AND PLACEMENT 4"
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.	SQ YD
	IL RTE 351						
STA. 247+00.00 TO STA. 262+30.70	1,212	69	961	919	29	13	4,957
STA. 262+30.70 TO STA. 52+90.57	1,802		1,352	499		853	2,353
CIVIC ROAD	624	134	569	96	30	443	1,204
N. 30TH ROAD	361	367	546	483	26	32	2,075
TOTAL	3,999	570	3,428	1,997	85	1,341	10,589

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
 SECTION (70XN & TS-1)
 LASALLE COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE: 08/13/04

DRAWN BY: BISHOP
 DESIGNED BY: KUNTZMAN
 CHECKED BY: COLBROOK

COMPUTER FILE NO.
 SCHEDULE_B-09
 PROJECT 01194_B.N
 08/13/04-RPB

GREENE & BRADFORD, INC.
 OF SPRINGFIELD
 REGISTERED PROFESSIONAL ENGINEERS
 LICENSE NO. 12152-1
 PROFESSIONAL DESIGN FIRM NO. 0011
 REGISTERED PROFESSIONAL LANDSCAPE ARCHITECTS
 LICENSE NO. 0011575, 0011576, 0011577, 0011578, 0011579, 0011580, 0011581, 0011582, 0011583, 0011584, 0011585, 0011586, 0011587, 0011588, 0011589, 0011590, 0011591, 0011592, 0011593, 0011594, 0011595, 0011596, 0011597, 0011598, 0011599, 0011600

REVISIONS	
NAME	DATE

FAU 6108 (IL. RTE. 351) LASALLE COUNTY