

CONTRACT NO. 90843

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY STPF TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X081-2A
20200100	EARTH EXCAVATION	CU YD	752
20300100	CHANNEL EXCAVATION	CU YD	2370
20400800	FURNISHED EXCAVATION	CU YD	574
20700220	POROUS GRANULAR EMBANKMENT	CU YD	424
20800150	TRENCH BACKFILL	CU YD	43
25000200	SEEDING, CLASS 2	ACRE	1.0
25000350	SEEDING, CLASS 7	ACRE	1.0
25000400	NITROGEN FERTILIZER NUTRIENT	POLND	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POLND	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
25100115	MULCH, METHOD 2	ACRE	1.0
25100630	EROSION CONTROL BLANKET	SQ YD	61
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100
28000300	TEMPORARY DITCH CHECKS	EACH	5
28000400	PERIMETER EROSION BARRIER	FOOT	352
28000500	INLET AND PIPE PROTECTION	EACH	12
28100107	STONE RIPRAP, CLASS A4	SQ YD	1635
28100109	STONE RIPRAP, CLASS A5	SQ YD	1683
28200200	FILTER FABRIC	SQ YD	338
3101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1391
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	347
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	26
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	734
40600300	AGGREGATE (PRIME COAT)	TON	15
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	364
40600990	TEMPORARY RAMP	SQ YD	149
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	246
42001300	PROTECTIVE COAT	SQ YD	1089
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	254
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	102
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	131
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	91
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4590
44000100	PAVEMENT REMOVAL	SQ YD	499
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	331
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	186

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY STPF TWO-LANE RURAL ROADWAY 80% FEDERAL 20% STATE X081-2A
44000600	SIDEWALK REMOVAL	SQ FT	3868
44000700	APPROACH SLAB REMOVAL	SQ YD	367
44002600	GUTTER OUTLET REMOVAL	FOOT	25
44004000	PAVED DITCH REMOVAL	FOOT	15
44004250	PAVED SHOULDER REMOVAL	SQ YD	164
48101200	AGGREGATE SHOULDERS, TYPE B	TON	35
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
50105210	REMOVE EXISTING CULVERTS	FOOT	72
50200100	STRUCTURE EXCAVATION	CU YD	1026
50300100	FLOOR DRAINS	EACH	42
50300150	NEOPRENE EXPANSION JOINT 2"	FOOT	227.0
50300225	CONCRETE STRUCTURES	CU YD	538.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	567.3
50300260	BRIDGE DECK GROOVING	SQ YD	1445
50300300	PROTECTIVE COAT	SQ YD	2014
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	26
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	2443
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	156670
51201000	FURNISHING METAL PILE SHELLS 12"	FOOT	3079
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1329
51201610	FURNISHING STEEL PILES HP12X63	FOOT	1446
51202600	DRIVING AND FILLING SHELLS	FOOT	3079
51202700	DRIVING STEEL PILES	FOOT	2775
51203200	TEST PILE METAL SHELLS	EACH	2
51203600	TEST PILE STEEL HP12X53	EACH	1
51203610	TEST PILE STEEL HP12X63	EACH	1
51205200	TEMPORARY SHEET PILING	SQ FT	1638
51500100	NAME PLATES	EACH	2

\* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**SHEET 1 OF 2**  
 DRAWN BY MLO  
 CHECKED BY SJK  
 DATE 5/03