

PATCHING SCHEDULE

PARTIAL DEPTH PAVEMENT PATCHING

STATION	DIRECTION	EXISTING OVERLAY THICKNESS (INCHES)	LENGTH (FT)	WIDTH (FT)	PARTIAL DEPTH REMOVAL (SQ YD)	BITUMINOUS MIXTURE FOR PATCHING (TON)
217+90.00A	EASTBOUND	4.5	10.00	12.25	13.61	5.72
217+90.00A	WESTBOUND	4.5	10.00	12.25	13.61	5.72
245+06.00A	EASTBOUND	4.5	4.00	12.25	5.44	2.29
245+06.00A	WESTBOUND	4.5	4.00	12.25	5.44	2.29
246+00.00A	EASTBOUND	4.5	4.00	12.25	5.44	2.29
246+00.00A	WESTBOUND	4.5	4.00	12.25	5.44	2.29
0+95.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
0+95.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
1+50.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
1+50.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
1+87.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
3+70.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
3+70.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
4+32.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
4+32.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
5+60.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
5+60.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
6+30.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
6+30.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
8+51.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
9+60.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
9+60.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
19+30.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
19+30.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
22+80.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
22+80.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
40+80.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
40+80.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
56+90.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
56+90.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
57+84.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
57+84.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
60+00.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
60+00.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
65+00.00	EASTBOUND	4.5	4.00	7.25	3.22	1.35
65+00.00	EASTBOUND	4.5	5.00	400.00	222.22	93.33
65+00.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
66+00.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
68+75.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
74+00.00	EASTBOUND	4.5	5.00	12.25	6.81	2.86
74+00.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
76+05.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
76+05.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
77+65.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
77+65.00	WESTBOUND	4.5	8.00	12.25	10.89	4.57
114+15.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
114+15.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
135+00.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
141+40.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
163+95.00	EASTBOUND	4.5	8.00	12.25	10.89	4.57
163+95.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
169+20.00	EASTBOUND	4.5	4.00	6.00	2.67	1.12
169+70.00	WESTBOUND	4.5	8.00	4.00	3.56	1.49
172+25.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
172+25.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
181+70.00	EASTBOUND	4.5	4.00	12.25	5.44	2.29
181+70.00	WESTBOUND	4.5	4.00	12.25	5.44	2.29
206+34.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
206+34.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
217+34.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
217+34.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43

PARTIAL DEPTH PAVEMENT PATCHING, CON'T.

STATION	DIRECTION	EXISTING OVERLAY THICKNESS (INCHES)	LENGTH (FT)	WIDTH (FT)	PARTIAL DEPTH REMOVAL (SQ YD)	BITUMINOUS MIXTURE FOR PATCHING (TON)
218+00.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
218+00.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
218+70.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
218+70.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
220+44.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
220+44.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
258+77.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
258+77.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
262+60.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
272+77.00	EASTBOUND	4.5	8.00	13.00	11.56	4.85
272+77.00	WESTBOUND	4.5	8.00	13.00	11.56	4.85
323+00.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
350+00.00	EASTBOUND	4.5	6.00	13.00	8.67	3.64
350+83.00	EASTBOUND	4.5	6.00	13.00	8.67	3.64
352+00.00	EASTBOUND	4.5	6.00	13.00	8.67	3.64
359+20.00	WESTBOUND	4.5	6.00	13.00	8.67	3.64
387+70.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
402+60.00	EASTBOUND	4.5	6.00	13.00	8.67	3.64
443+00.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
454+50.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
522+15.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
545+00.00	EASTBOUND	4.5	6.00	13.00	8.67	3.64
577+69.00	EASTBOUND	4.5	4.00	13.00	5.78	2.43
589+65.00	WESTBOUND	4.5	4.00	13.00	5.78	2.43
TOTAL =						739.47 SQ YD 310.58 TON
USE =						740.00 SQ YD 311.00 TON

CLASS D PAVEMENT PATCH, 13 INCH

STATION	DIRECTION	LOCATION	LENGTH (FT)	WIDTH (FT)	PATCH AREA	
					TYPE II (SQ YD)	TYPE III (SQ YD)
474+00.00	WESTBOUND	MAINLINE	12.00	13.00	0.00	17.33
521+00.00	EASTBOUND	MAINLINE	6.00	13.00	8.67	0.00
569+55.00	EASTBOUND	MAINLINE	8.00	13.00	11.56	0.00
TOTAL =						20.22 17.33
USE =						21.00 18.00
						(SQ YD) (SQ YD)