

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(11,12)RS-2	DEWITT	53	39

CONTRACT NO. 90867

PAINT PAVEMENT MARKING - LINE 4 "

ROUTE	STATION	TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" SOLID NO PASSING YELLOW (FOOT)	LANE
IL 54	451+94.09		619+13.40	BK.	16,719.31	33,438.62	4,179.83	
IL 54	619+12.43	AH.	650+33.95	BK.	3,121.52	6,243.04	780.38	
IL 54	650+30.70	AH.	670+89.90		2,059.20	4,118.40	514.80	
IL 54	670+89.90		676+70.70		580.80	1,161.60	145.20	EB
IL 54	676+70.70		687+79.50		1,108.80	2,217.60	277.20	WB
IL 54	687+79.50		730+56.30		4,276.80	8,553.60	1,069.20	
IL 54	730+56.30		742+17.90		1,161.60	2,323.20	290.40	EB
IL 54	742+17.90		755+37.90		1,320.00	2,640.00	330.00	WB
IL 54	755+37.90		769+10.70		1,372.80	2,745.60	343.20	
IL 54	769+10.70		773+98.40	BK.	487.70	975.40	121.92	EB
IL 54	774+08.40	AH.	779+36.40		528.00	1,056.00	132.00	EB
IL 54	779+36.40		785+17.20		580.80	1,161.60	0.00	EB/WB
IL 54	785+17.20		789+86.80	BK.	469.60	939.20	117.40	WB
IL 54	790+01.40	AH.	792+65.40		264.00	528.00	66.00	WB
IL 54	792+65.40		887+16.67	BK.	9,451.27	18,902.54	2,362.82	
IL 54	887+16.00	AH.	894+02.40		686.40	1,372.80	171.60	
IL 54	894+02.40		899+30.40		528.00	1,056.00	132.00	EB
IL 54	899+30.40		904+58.40		528.00	1,056.00	132.00	
IL 54	904+58.40		909+86.40		528.00	1,056.00	132.00	WB
IL 54	909+86.40		970+49.68	BK.	6,063.28	12,126.56	1,515.82	
IL 54	970+42.50	AH.	975+16.82		474.32	948.64	118.58	
TOTAL =					52,310.20	104,620.40	12,932.35	8,138.10
					USE =	125,691.00		