

## SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	5

\* (58-62,58-62-1,58-63)RS  
CONTRACT NO. 90879

LOCATION OF WORK: FAI ROUTE 72 (I-72)  
SECTION (58-62, 58-62-1, 58-63)RS  
MACON COUNTY

FAI 72  
IL 121  
Macon  
County  
Sta 878+24.32  
to  
Sta 920+60.90

FAI-72 Macon County    FAI-72 Macon County    FAI-72 Macon County    FAI-72 Macon County    FAI-72 Macon County    FAI-72 Macon County    FAI-72 Macon County

Sta 415+07.22 to Sta 468+58.30    Sta 468+58.30 to Sta 861+36.68    Impact Attenuators SN 058-0069    SN 058-0070 & SN 058-0071    SN 058-0074 & SN 058-0075

Rural	Urban	Urban	Urban	Urban	Urban	Urban
90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	I000

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	I000
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1.0	0.5	0.5	0.0	0.0	0.0	0.0	0.0
<del>E0006150</del>	BRIDGE DECK HYDRO-SCARIFICATION	SQ YD	8630.0	0.0	0.0	0.0	2867.0	2096.0	3667.0	0.0
20200100	EARTH EXCAVATION	CU YD	401.0	0.0	401.0	0.0	0.0	0.0	0.0	0.0
20400800	FURNISHED EXCAVATION	CU YD	2445.0	0.0	2445.0	0.0	0.0	0.0	0.0	0.0
21400100	GRADING AND SHAPING DITCHES	FOOT	980.0	0.0	830.0	0.0	0.0	0.0	0.0	150.0
25000210	SEEDING, CLASS 2A	ACRE	4.0	0.1	3.9	0.0	0.0	0.0	0.0	0.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	400.0	9.0	391.0	0.0	0.0	0.0	0.0	0.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	400.0	9.0	391.0	0.0	0.0	0.0	0.0	0.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	400.0	9.0	391.0	0.0	0.0	0.0	0.0	0.0
25100115	MULCH, METHOD 2	ACRE	4.0	0.1	3.9	0.0	0.0	0.0	0.0	0.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	413.0	10.0	403.0	0.0	0.0	0.0	0.0	0.0
28000300	TEMPORARY DITCH CHECKS	EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1589.0	0.0	1589.0	0.0	0.0	0.0	0.0	0.0
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	297.0	0.0	297.0	0.0	0.0	0.0	0.0	0.0
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	103.0	0.0	0.0	0.0	0.0	0.0	0.0	103.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	130.0	42.0	88.0	0.0	0.0	0.0	0.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25940.0	3028.0	21667.0	0.0	0.0	0.0	0.0	1245.0
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GALLON	50878.0	6635.0	40820.0	0.0	0.0	0.0	0.0	3423.0
40600300	AGGREGATE (PRIME COAT)	TON	1538.0	194.0	1248.0	0.0	0.0	0.0	0.0	96.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	11589.0	1019.0	10368.0	0.0	0.0	0.0	0.0	202.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	942.0	240.0	379.0	0.0	0.0	0.0	0.0	323.0
40600990	TEMPORARY RAMP	SQ YD	2458.0	467.0	1929.0	0.0	0.0	0.0	0.0	62.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	98.0	0.0	22.0	0.0	0.0	0.0	0.0	76.0
40800030	AGGREGATE (PRIME COAT)	TON	2.0	0.0	1.0	0.0	0.0	0.0	0.0	1.0
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	316.0	0.0	175.0	0.0	0.0	0.0	0.0	141.0
42001300	PROTECTIVE COAT	SQ YD	152.0	0.0	152.0	0.0	0.0	0.0	0.0	0.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	1556.0	0.0	1556.0	0.0	0.0	0.0	0.0	0.0
44000300	CURB REMOVAL	FOOT	42.0	0.0	42.0	0.0	0.0	0.0	0.0	0.0