

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	•	MACON	135	25

• (58-62,58-62-1,58-63)RS
CONTRACT NO. 90879

TABULATION OF CLASS A PAVEMENT PATCHING I-72 EASTBOUND - 8" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (FT)	PATCH AREA				SAW CUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	PATCHING REINFORCEMENT 44213000 (SQYD)	STAB SHLDR REPAIR Z0066800 (SQ YD)	
				WIDTH (FT)	TYPE I 44200525 (SQ YD)	TYPE II 44200529 (SQ YD)	TYPE III 44200533 (SQ YD)					TYPE IV 44200535 (SQ YD)
626+25	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
627+95	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
630+10	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
636+90	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
637+35	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
645+27	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
645+55	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
646+07	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
646+70	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
672+85	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
676+45	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
715+45	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
717+47	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
730+05	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
739+35	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
1763+30	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1764+94	EB	DL	10.0	6.0		6.7			44.0	0.0	6.7	70.0
1765+25	EB	DL	30.0	6.0			20.0		84.0	30.0	20.0	76.7
1765+55	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1767+47	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1768+10	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1769+30	EB	DL	8.0	12.0		10.7			64.0	0.0	10.7	69.3
1769+40	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1773+20	EB	DL	10.0	6.0		6.7			44.0	0.0	6.7	70.0
1773+75	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1773+90	EB	DL	7.0	12.0		9.3			62.0	0.0	9.3	69.0
1777+20	EB	DL	10.0	6.0		6.7			44.0	0.0	6.7	70.0
1777+50	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1777+73	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1777+85	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1777+95	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1778+05	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1778+15	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1778+45	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
1778+60	EB	DL	25.0	6.0			16.7		74.0	25.0	16.7	75.0
1779+20	EB	DL	15.0	6.0		10.0			54.0	0.0	10.0	71.7
1780+80	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1783+15	EB	DL	10.0	6.0		6.7			44.0	0.0	6.7	70.0
1785+60	EB	DL	10.0	6.0		6.7			44.0	0.0	6.7	70.0
1787+05	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1796+15	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1805+00	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1805+60	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1807+90	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
1808+90	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
818+35	EB	PL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
824+90	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
827+70	EB	DL	15.0	6.0		10.0			54.0	0.0	10.0	71.7
835+75	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
838+30	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
845+80	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
846+95	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
850+90	EB	DL	4.5	12.0		6.0			57.0	0.0	6.0	68.2
851+75	EB	DL	6.0	12.0		8.0			60.0	0.0	8.0	68.7
857+72	EB	DL	25.0	12.0					98.0	25.0	33.3	75.0
SHEET TOTALS =				0.0		289.3	36.7	33.3	2666.0	80.0	359.3	3179.0
EASTBOUND FINAL TOTAL =				14.5		862.7	60.0	73.3	7842.0	145.0	1010.5	9510.3
WESTBOUND FINAL TOTAL =				8.0		817.7	118.0	246.7	8605.0	407.0	1190.3	9892.5
TOTAL =				22.5		1680.3	178.0	320.0	16447.0	552.0	2200.8	19402.8
FINAL TOTAL =				23.0		1681.0	178.0	320.0	16447.0	552.0	2201.0	19403.0