

SUMMARY OF QUANTITIES

SHEET 1 OF 2

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320		MACON	51	4

(126X) RS-1&135(R) RS&(BR-1) BRJ
CONTRACT NO. 90926

LOCATION OF WORK:

URBAN
STA. 1024+00
TO STA. 45+58
80% FED.
20% STATE
1000-2A

URBAN
S. N. 058-0050
IL 48 OVER
SPRING CREEK
80% FED.
20% STATE
SFTY-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY		
60260510	INLETS TO BE ADJUSTED WITH NEW TYPE 3 GRATE	EACH	10.0	10.0	
60261325	INLETS TO BE ADJUSTED WITH NEW TYPE 11 GRATE	EACH	94.0	94.0	
20006150	BRIDGE DECK HYDRO-SCARIFICATION	SQ YD	1,014.0		1,014.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15,602.0	15,602.0	
40600300	AGGREGATE (PRIME COAT)	TON	312.0	312.0	
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1,070.0	1,070.0	
40600990	TEMPORARY RAMP	SQ YD	2,242.0	2,242.0	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	172.0	172.0	
40800030	AGGREGATE (PRIME COAT)	TON	4.0	4.0	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	193.0	193.0	
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	30,899.0	30,899.0	
44000012	BITUMINOUS SURFACE REMOVAL 4 1/2"	SQ YD	12,360.0	12,360.0	
44000300	CURB REMOVAL	FOOT	259.0	259.0	
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	1,014.0		1,014.0
44001300	BITUMINOUS CONCRETE SURFACE REMOVAL (SPECIAL)	SQ YD	899.0	899.0	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400.0	400.0	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	466.0	466.0	
44002805	ISLAND REMOVAL	SQ FT	502.0	502.0	
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	678.0	678.0	
44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQ YD	17.0	17.0	
50300260	BRIDGE DECK GROOVING	SQ YD	1,014.0		1,014.0
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12.0		12.0
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12.0		12.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4,130.0		4,130.0
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	24.0		24.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	10.0		10.0
60255500	MANHOLES TO BE ADJUSTED	EACH	8.0	8.0	
60260100	INLETS TO BE ADJUSTED	EACH	15.0	15.0	
60401810	GRATES, TYPE 3	EACH	3.0	3.0	
60402510	GRATES, TYPE 11	EACH	12.0	12.0	
60622354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SQ FT	671.0	671.0	
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ FT	696.0	696.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6.0	6.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.0	1.0	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	1.0	