

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	344	6B
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
*107WRS-1, 107BY, 107BY-1 & 107B-2		CONTRACT NO. 94827		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y030-IE		Y031-IF	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN	RURAL	URBAN	
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS & SYMBOLS	SO FT	73	73									
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	92,863	79,604	13,259								
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	1,830	1,830									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	57,773	49,310	8,463								
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1,231	633	598								
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1,181	633	548								
* 72000100	SIGN PANEL - TYPE 1	SO FT	9								9		
* 72000200	SIGN PANEL - TYPE 2	SO FT	62								62		
* 73000100	WOOD SIGN SUPPORT	FOOT	18								18		
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1,846	1,451	395								
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	88,914	76,170	12,744								
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	8,388	6,942	1,446								
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	4,208	4,208									
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	225	73	152								
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,661	1,364	297								
* 78200405	GUARDRAIL MARKERS	EACH	21	16	5								
* 78200500	BARRIER WALL MARKERS	EACH	10	5	5								
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	3	5								
78300500	PAINT PAVEMENT MARKING REMOVAL	SO FT	12,224	10,772	1,452								
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	4						3	1			
* 80500200	SERVICE INSTALLATION, TYPE B	EACH	1								1		
* 80802100	WOOD POLE, 35 FT., CLASS 4	EACH	1								1		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1,530						258	1,197	75		
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	775								775		
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	7							7			
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	123								123		
* 81013200	CONDUIT IN TRENCH, 6" DIA., PVC	FOOT	8								8		
* 81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	848						546	302			
* 81021340	CONDUIT, PUSHED, 2 1/2" DIA., PVC	FOOT	435								435		
* 81021370	CONDUIT, PUSHED, 4" DIA., PVC	FOOT	145								145		
* 81021390	CONDUIT, PUSHED, 6" DIA., PVC	FOOT	98								98		
* 81400100	HANDHOLE	EACH	7								7		
* 81400300	DOUBLE HANDHOLE	EACH	2							1	1		
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,443						258	1,204	981		
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	8,829						2,463	6,366			
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	456						345	111			
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4							4			
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	15						8	7			
* 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP-240 VOLT	EACH	4						3	1			
* 8300640	LIGHT POLE, FIBERGLASS, 45 FT. M.H., TENON MOUNT	EACH	15						8	7			
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	120						64	56			
* 83800505	BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT	EACH	60						32	28			
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1								1		
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	2								2		
* 87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	1,366								1,366		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	244								244		
* 87301235	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 4C	FOOT	270								270		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,125								2,125		
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	801								801		
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	54								54		

@ SN 025-007B
 @ @ SN 025-0077
 @ @ @ SN 025-3309

 Δ Δ SFTY -3C

NOTE:
 RURAL STA. 541+93.85 TO STA. 1016+00.00
 URBAN STA. 1016+00.00 TO STA. 46+80.05
 * DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

 SUMMARY OF QUANTITIES
 SHEET 5 OF 8

 DATE 8/02
 DRAWN BY ASB
 CHECKED BY SJK