F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	**	189	63
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

* X1-2,44(2,3,4)RS,BSMARTFY04-4
** WILLIAMSON/JOHNSON
CONTRACT NO.: 98758

RIPRAP

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	STONE RIPRAP DITCH	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A4	STONE DUMPED RIPRAP CLASS A5	STONE RIPRAP CLASS A3	STONE RIPRAP CLASS A4	GABIONS PAY ITEM	GABIONS INFORMATION ONLY (SEE NOTE 1) AVERAGE LENGTH	WIDTH	HEIGHT	EST. NO. OF CELLS	FILTER FABRIC (SEE NOTE 2)	RIPRAP SLURRY	REMARKS
	TON	SQ YD	TON	TON	TON	TON	CU YD	FT	FT	FT	CELLS	SQ YD	SQ YD	
EB LANES														
RT 392+50 TO 395+50 (MP 6.8)					48									BEHIND CONCRETE CURB
RT 393+68 TO 394+57 (MP 6.8)	47													
RT 395+34 TO 396+60 (MP 6.8)														
RT 395+14 TO 399+35 (MP 6.9)	246													
RT 473+21 TO 473+55 (MP 8.2)	26													
RT 481+48 TO 484+15 (MP 8.4)	155													
RT 486+43 (MP 8.5)							9	9	18	1.5	18			SEE SCOUR REPAIR DETAIL SHEET 161
RT 487+50 (MP 8.5)					87							174.4		
RT 485+50 TO 490+00 (MP 8.6)					91									BEHIND CONCRETE CURB
RT 490+00 (MP 8.6)												178.0		
RT 490+00 (MP 8.6)					87									
RT 518+00 TO 520+70 (MP 9.2)	151													
RT 107+75 (MP 9.3)					28									
RT 113+92 (MP 9.4)				22										
RT 111+00 TO 116+00 (MP 9.5)					117									BEHIND CONCRETE CURB
RT 115+35 (MP 9.5)					78							155.6		
RT 136+82 TO 141+25 (MP 9.9)	242													
RT 138+35 TO 139+53 (MP 9.9)					131									
RT 143+58 TO 155+03 (MP 10.2)	636													
RT 181+50 (MP 10.7)					56							111.0		
RT 180+50 TO 186+09 (MP 10.8)					119									BEHIND CONCRETE CURB
RT 180+55 TO 185+53 (MP 10.8)	306												611.1	RIPRAP SLURRY
RT 184+00 (MP 10.8)	28												55.6	RIPRAP SLURRY
RT 184+10 (MP 10.8)							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
RT 185+00 (MP 10.8)					67							133.3		
RT 191+54 (MP 10.9)					47							94.4		
RT 187+40 TO 196+02 (MP 11.0)					138									BEHIND CONCRETE CURB
RT 194+72 TO 197+98 (MP 11.0)	181													
RT 194+84 TO 195+20 (MP 11.0)					9									
RT 195+20 TO 195+47 (MP 11.0)					30									
RT 195+47 TO 196+19 (MP 11.0)					120									
RT 195+97 (MP 11.0)					42							83.3		
RT 225+98 TO 231+50 (MP 11.7)	332													
RT 231+25 (MP 11.7)					62							124.4		
RT 231+60 (MP 11.7)							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
RT 232+22 (MP 11.7)							6	6	9	3	6			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
RT 233+10 (MP 11.7)							8	6	12	3	8			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
RT 234+95 (MP 11.7)							4	6	6	3	4			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
RT 235+00 (MP 11.7)					17							33.3		
RT 229+75 TO 238+75 (MP 11.8)					179									BEHIND CONCRETE CURB
RT 238+75 (MP 11.8)												111.0		
RT 238+63 TO 241+03 (MP 11.8)	134													
RT 249+55 TO 250+27 (MP 12.0)	52													
RT 269+39 TO 270+29 (MP 12.4)	53													
RT 270+70 TO 279+53 (MP 12.6)	498													
RT 283+73 (MP 12.6)			111											STONE RIPRAP DITCH OVER 5' DEEP, A4 RIPRAP
RT 283+73 (MP 12.6)	31													
RT 292+20 TO 293+54 (MP 12.8)	74												149.0	RIPRAP SLURRY
RT 301+00 (MP 13.0)	25													
LT 373+34 TO 373+91 (MP 6.4)	40													
LT 395+34 TO 396+60 (MP 6.8)	74												149.0	
LT 182+00 (MP 10.7)					50							100.0		
LT 180+00 TO 186+14 (MP 10.8)					110									BEHIND CONCRETE CURB
LT 182+90 (MP 10.8)							9	9	9	3	9			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
LT 183+60 (MP 10.8)							8	6	12	3	8			DOWN FORESLOPE BEHIND GUARDRAIL - SEE SAFETY PLANS
LT 184+50 (MP 10.8)					61							122.0		
LT 186+10 (MP 10.8)					61							122.2		
LT 188+01 TO 189+64.5 (MP 10.9)	83													
LT 189+73 (MP 10.9)					75							150.0		

Revised Sheet 3-2-05

*DATE-TIME-FEBRUARY 25,2005
C:/PROJECT/09020/SCW1A32

SCHEDULE: RIPRAP