

QU093

G:\AIRPORT\A04T015\SUMQUAN.DWG, 1=1 12.15.04

QUAD CITY INTERNATIONAL AIRPORT  
 RUNWAY 5-23 OVERLAY, PHASE I  
 ILL. MLI-3374

SHEET 2 OF 63

## SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITIES	
			AS AWARDED	AS BUILT
AR108158	1/C, #8, 5KV, UG CABLE IN UNIT DUCT	L.F.	1,410	
AR108258	2/C, #8, 5KV, UG CABLE IN UNIT DUCT	L.F.	280	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	17	
AR125415	MITL, BASE MOUNTED	EACH	8	
AR125906	REMOVE SPLICE CAN	EACH	1	
AR125942	ADJUST BASE MOUNTED LIGHT	EACH	20	
AR125943	ADJUST INPAVEMENT LIGHT	EACH	9	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	1	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EACH	1	
AR125966	RELOCATE SPLICE CAN	EACH	1	
AR150512	ENGINEER'S FIELD OFFICE-MONTHLY	C.M.	9	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	240	
AR152419	UNCLASSIFIED DISPOSAL OFFSITE	C.Y.	645	
AR152443	OFFSITE TOPSOIL	C.Y.	610	
AR156500	TEMPORARY EROSION CONTROL	L.S.	1	
AR209510	CRUSHED AGGREGATE BASE CRSE.	TON	1,390	
AR209511	CRUSHED AGGREGATE BASE, CA1	TON	100	
AR209600	GEOTEXTILE FABRIC	S.Y.	2,700	
AR401610	BITUMINOUS SURFACE COURSE	TON	6,500	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	35,650	
AR402620	POROUS FRICTION COURSE 5/8"	S.Y.	33,600	
AR402621	POROUS FRICTION COURSE 1"	S.Y.	4,500	
AR402630	POROUS FRICTION COURSE TEST SECTION	EACH	1	
AR501508	8" PCC PAVEMENT	S.Y.	12,400	
AR501509	9" PCC PAVEMENT	S.Y.	6,550	
AR501530	PCC TEST BATCH	EACH	1	
AR501540	PCC PAVEMENT GROOVING	S.Y.	15,250	
AR501900	REMOVE PCC PAVEMENT	S.Y.	1,860	
AR603510	BITUMINOUS TACK COAT	GAL.	14,103	
AR620510	PAVEMENT MARKING	S.F.	18,250	
AR620595	TEMPORARY MARKING & REMOVAL	S.F.	1,125	
AR751944	ADJUST MANHOLE - PAVEMENT	EACH	5	
AR751945	ADJUST MANHOLE - NON PAVEMENT	EACH	4	
AR751983	RECONSTRUCT MANHOLE	EACH	1	
AR800824	SURFACE SENSOR INSTALLATION	L.S.	1	
AR801605	REPLACE TAXI GUIDANCE SIGN PANEL	EACH	10	
AR801606	SCAN SYSTEM UPGRADE	L.S.	1	
AR801607	STAND-BY TIME	EACH	10	
AR801608	BITUMINOUS TACK COAT TEST SECTION	EACH	4	
AR901510	SEEDING	ACRE	4	

### GENERAL NOTES:

1. MAXIMUM PAY WIDTH FOR 209 GRANULAR BASE SHALL BE 12 INCHES BEYOND THE EDGE OF PAVEMENT. IF THE CONTRACTOR REQUIRES ADDITIONAL WIDTH FOR PAVEMENT INSTALLATION, THE ADDITIONAL MATERIALS SHALL MEET THE SAME SPECIFICATIONS, BUT WILL BE CONSIDERED INCIDENTAL.
2. THE CONTRACTOR SHALL SALVAGE EXISTING AIRFIELD LIGHTING EQUIPMENT AS DETAILED IN THE CONSTRUCTION PLANS AND SPECIAL PROVISIONS PRIOR TO THE START OF EARTHWORK AND/OR PAVING ACTIVITIES. SALVAGED EQUIPMENT SHALL BE CLEANED AND REUSED OR DELIVERED TO THE METROPOLITAN AIRPORT AUTHORITY.
3. CROSS SECTION SLOPES, CENTERLINE PROFILE GRADES, AND ALL SPOT GRADES SHALL BE SUBJECT TO CHANGE, AS APPROVED BY THE RESIDENT ENGINEER, AT THE TIME OF CONSTRUCTION.
4. THE CONTRACTOR SHALL EXCAVATE TEMPORARY EROSION CONTROL DRAINAGE SWALES, AS REQUIRED BY THE ENGINEER, TO CONTROL STORM WATER RUN-OFF.
5. THE CONTRACT 152 - EARTHWORK ITEMS SHALL INCLUDE ALL COSTS ASSOCIATED WITH EXCAVATION OF SOILS, HAULING OF SOILS, STOCKPILING SOILS, INSTALLATION OF SOILS, COMPACTION OF SOILS, GRADING OF SOILS, INSTALLATION AND REMOVAL OF HAUL ROADS OR ROUTES, RESTORATION OF HAUL ROADS OR ROUTES, DISPOSAL OF WASTE SOILS, CLEANING OF PAVEMENTS, AND ALL OTHER ITEMS THAT ARE REQUIRED TO COMPLETE THE EARTHWORK. THESE ITEMS SHALL BE PAID FOR BASED UPON THE CUBIC YARDS OF MATERIALS REMOVED AND/OR REQUIRED AS ACCEPTED BY THE ENGINEER. SEE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.
6. AFTER CONSTRUCTION HAS BEEN COMPLETED, THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS PER SPECIAL PROVISION 901. ONLY SEED AREAS WITHIN THE LIMITS OF CONSTRUCTION/SEEDING WILL BE ELIGIBLE FOR PAYMENT UNDER THE CONTRACT PAY ITEM. AREAS OUTSIDE OF THE LIMITS OF CONSTRUCTION/SEEDING SHALL BE SEEDED BY THE CONTRACTOR PER SPECIAL PROVISION 901, BUT SHALL NOT BE MEASURED FOR PAYMENT.