


# SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	APRON / STOPWAY		ROAD / PARKING LOT		TOTAL	
			ESTIMATED	RECORD	ESTIMATED	RECORD	ESTIMATED	RECORD
AR107920	REPLACE WIND CONE	EACH	1				1	
AR108108	1/C #8 5 KV UG CABLE	LF	255				255	
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	2,780				2,780	
AR110212	2" STEEL DUCT, DIRECT BURY	LF	330				330	
AR110502	2-WAY CONCRETE ENCASED DUCT	LF	110				110	
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	230				230	
AR110550	SPLIT DUCT	LF	35		25		60	
AR110610	ELECTRICAL HANDHOLE	EACH			1		1	
AR110900	REMOVE DUCT	LF	120				120	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	9				9	
AR125410	MIL - STAKE MOUNTED	EACH	14				14	
AR125415	MIL - BASE MOUNTED	EACH	4				4	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1				1	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	1				1	
AR125585	SPUCE CAN	EACH	1				1	
AR125947	ADJUST REILS	PAIR	1				1	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	8				8	
AR150510	ENGINEER'S FIELD OFFICE	LS	1				1	
AR151450	CLEARING AND GRUBBING	ACRE	5				5	
AR152410	UNCLASSIFIED EXCAVATION	CY	76,999		14,176		91,175	
AR155712	LIME-MODIFIED SUBGRADE - 12"	SY	16,235				16,235	
AR156510	SILT FENCE	LF	2,925		2,275		5,200	
AR156511	DITCH CHECK	EACH	4				4	
AR156512	BALES	EACH	65		115		180	
AR156540	RIPRAP	SY			120		120	
AR162506	CLASS E FENCE 6'	LF	3,670				3,670	
AR162616	CLASS E GATE-16'	EACH	3				3	
AR163520	CONSTRUCTION FENCE	LF	600				600	
AR201610	BITUMINOUS BASE COURSE	TON	3,924		1,666		5,590	
AR201630	BITUMINOUS BASE TEST SECTION	EACH	1				1	
AR208515	POROUS GRANULAR EMBANKMENT	CY	2,175		25		2,200	
AR209604	CRUSHED AGG. BASE COURSE - 4"	SY	22,256				22,256	
AR401610	BITUMINOUS SURFACE COURSE	TON			1,105		1,105	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	185		25		210	
AR501509	9" PCC PAVEMENT	SY	5,610				5,610	
AR501512	12" PCC PAVEMENT	SY	15,410				15,410	
AR501530	PCC TEST BATCH	EACH	1				1	
AR501540	PCC PAVEMENT GROOVING	SY	4,485				4,485	
AR501604	4" PCC SIDEWALK	SF			1,395		1,395	
AR510515	GROUND ROD	EACH	4				4	
AR602510	BITUMINOUS PRIME COAT	GAL	4,660		3,605		8,265	
AR603510	BITUMINOUS TACK COAT	GAL			1,800		1,800	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	4,625		645		5,270	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	2,095				2,095	
AR701006	6" PVC STORM SEWER	LF	350				350	
AR701512	12" RCP, CLASS IV	LF	867				867	
AR701515	15" RCP, CLASS IV	LF			60		60	
AR701518	18" RCP, CLASS IV	LF			120		120	
AR701530	30" RCP, CLASS IV	LF			240		240	
AR701900	REMOVE PIPE	LF	360				360	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	LF	3,350				3,350	
AR705635	UNDERDRAIN COLLECTION STRUCTURE	EACH	6				6	
AR705900	REMOVE UNDERDRAIN	LF	305				305	
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	1				1	
AR751540	MANHOLE 4'	EACH	1				1	
AR751600	CATCH BASIN	EACH	2				2	
AR751903	REMOVE MANHOLE	EACH	1				1	
AR752415	PRECAST REINFORCED CONC. FES 15"	EACH			2		2	
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH			4		4	
AR752430	PRECAST REINFORCED CONC. FES 30"	EACH			8		8	
AR752515	GRATING FOR CONC. FES 15"	EACH			2		2	
AR752518	GRATING FOR CONC. FES 18"	EACH			4		4	
AR752530	GRATING FOR CONC. FES 30"	EACH			8		8	
AR754410	COMB CONCRETE CURB & GUTTER	LF			665		665	
AR770908	REMOVE SEPTIC SYSTEM	LS	1				1	
AR800009	HAUL ROAD AGGREGATE BASE	SY			12,995		12,995	
AR800019	FRESH WATER WELL ABANDONMENT	EACH	1				1	
AR800026	SLOPE BOX INLET 12"	EACH	3				3	
AR800033	TREE CLEARING AND GRUBBING (6"-15")	IN-DIA	1,225				1,225	
AR800034	TREE CLEARING AND GRUBBING (+15")	IN-DIA	492				492	
AR800053	SOIL GUARD	SY	15,125				15,125	
AR800071	PIPE RESTRICTOR	EACH	2				2	
AR800091	TWO-WAY AMBER CENTERLINE REFLECTOR	EACH			70		70	
AR800101	DELINEATOR	EACH			92		92	
AR800102	FOUNDATION REMOVAL	SY	2,840				2,840	
AR800140	2 1/C #8XLP-USE, 1/C #10 GND - 1" UD	LF			225		225	
AR800145	LOCALIZER GROUND CHECK POINT	EACH	10				10	
AR800152	EXPLORATORY TRENCH	LF	75				75	
AR800158	3-1/C #6 XLP-USE 600V, 1/C #8 GND IN UD	LF	970				970	
AR800161	REFUSE REMOVAL	LS	1				1	
AR800165	SEPERATION FABRIC	SY	5,735				5,735	
AR901510	SEEDING	ACRE	24.5		5.0		29.5	
AR904510	SODDING	SY	1,040				1,040	
AR908510	MULCHING	ACRE	22.5		5.0		27.5	
AR910101	ROADWAY LIGHT POLE, TYPE A	EACH			2		2	
AR910121	ROADWAY LIGHT FIXTURE, TYPE A	EACH			2		2	
AR910200	ROADWAY SIGN	EACH			6		6	

REVISIONS

NUMBER	BY	DATE



**AURORA MUNICIPAL AIRPORT  
 AURORA, ILLINOIS  
 CONSTRUCT NORTHEAST QUADRANT APRON,  
 CONNECTING TAXIWAY AND RUNWAY 27 STOPWAY**

**SUMMARY OF QUANTITIES**

© Copyright GMT, Inc.  
**GMT**  
 CRAWFORD, MURPHY & TILLY, INC.  
 CONSULTING ENGINEERS  
 License No. 184-000518

DESIGN BY:	DKP
DRAWN BY:	JRO
CHECKED BY:	MJS
APPROVED BY:	DKP
DATE:	01/26/05
JOB No:	04285-03
ILLINOIS PROJECT: ARR-3442 A.I.P. PROJECT: 3-17-0003-B30 <b>FINAL SUBMITTAL</b>	
SHEET	2 OF 39 SHEETS