

CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY	PEORIA URBAN	KNOX RURAL
67100100	MOBILIZATION	L SUM	1.00	0.50	0.50
X7010210	TRAFFIC CONTROL & PROTECTION (SPECIAL)	L SUM	1.00	0.50	0.50
73300200	OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A (4'-6" X 5'-3")	FOOT	94.00		94.00
73302170	OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	30.00		30.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7.12		7.12
73600100	REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00		1.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00		1.00
73700300	REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00		1.00
73801100	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00	1.00	
T9990205	FURNISH AND ERECT SIGN PANEL	SQ FT	4,124.00	3,574.00	550.00
T9990710	REMOVE AND REINSTALL WALKWAY	FOOT	163.50		163.50
T9991300	REMOVE EXISTING SIGN PANEL	EACH	17.00	14.00	3.00
T9992530	REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER EACH SIGN	EACH	7.00	2.00	5.00
T9995010	REMOVE AND RE-ERECT OVERHEAD SIGN END SUPPORT	EACH	2.00	2.00	
T9995200	REPLACE U-BOLT	EACH	3.00		3.00
T9995210	TIGHTEN U-BOLT	EACH	3.00	3.00	
T9995400	FURNISH AND INSTALL SADDLE BLOCK	EACH	4.00		4.00
T9996200	REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	4.00	4.00	
T9996300	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00	4.00	
T9997255	FURNISH AND INSTALL TRUSS DAMPER	EACH	1.00		1.00
T9997700	FURNISH AND INSTALL SAFETY CHAIN	EACH	12.00	6.00	6.00
T9998105	REPLACE HAND-HOLE COVER BOLT	EACH	8.00	2.00	6.00
T9998300	TIGHTEN SPLICE FLANGE	EACH	1.00	1.00	
T9998600	TIGHTEN CANTILEVER CONNECTION	EACH	1.00	1.00	
T9998700	FURNISH AND INSTALL WALKWAY TIE DOWN BOLTS	EACH	1.00	1.00	
T9998815	REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	36.00	26.00	10.00
T9998910	FURNISH AND INSTALL METAL SCREEN	EACH	1.00		1.00
T9998992	RELOCATE ELECTRIC SERVICE	L SUM	1.00		1.00
T9998995	DISCONNECT AND RECONNECT ELECTRIC SERVICE	EACH	6.00	3.00	3.00
X0321631	REMOVAL OF LUMINAIRE	EACH	21.00	12.00	9.00
X0323583	SPEED INDICATOR SIGN	CAL DA	40.00	20.00	20.00
X7330100	PAINT OVERHEAD SIGN SUPPORT	EACH	12.00	8.00	4.00

FILE NAME :
WPLLS

USER NAME : USER0	DESIGNED -	REVISED -
PLOT SCALE : 1/8"=1'-0"	CHECKED -	REVISED -
PLOT DATE : 11/20/20	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 2 OF 30 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Peoria-4 OVD SM STR REPL II-20	INDO-PEORIA	INDO-PEORIA	30	2
CONTRACT NO. 46152			ILLINOIS FED. AID PROJECT	