

Location No.	4-01	State I.D. No.	4S048U034L008.0		
County	KNOX	Route	US 34	M.P.	8.00
Direction	WB	Unit	Quantity		
Description of Work					
REMOVE AND REINSTALL WALKWAY		FOOT	145.00		
REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER SIGN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A		FOOT	94.00		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
FURNISH AND ERECT SIGN PANEL		SQ FT	176.00		
REMOVE LUMINAIRE		EACH	4.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		
FURNISH AND INSTALL SAFETY CHAIN		EACH	2.00		

Location No.	4-04	State I.D. No.	4S072H74L001.10		
County	PEORIA	Route	I-474	M.P.	1.10
Direction	WB	Unit	Quantity		
Description of Work					
REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER SIGN		EACH	1.00		
REPLACE HAND-HOLE COVER BOLT		EACH	4.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	12.00		
FURNISH AND ERECT SIGN PANEL		SQ FT	625.75		
TIGHTEN SPLICE FLANGE		EACH	1.00		
REMOVE LUMINAIRE		EACH	4.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		
FURNISH AND INSTALL SAFETY CHAIN		EACH	2.00		

Location No.	4-07	State I.D. No.	4S072S006L000.50		
County	PEORIA	Route	IL 6	M.P.	0.50
Direction	SB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	393.00		
REMOVE EXISTING SIGN PANEL		EACH	3.00		

Location No.	4-10	State I.D. No.	4C072H74L000.40		
County	PEORIA	Route	I-474	M.P.	0.4
Direction	WB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	125.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		

Location No.	4-02	State I.D. No.	4C048U150L011.9		
County	KNOX	Route	US 150	M.P.	11.9
Direction	WB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	75.00		
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A		FOOT	39.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	7.12		
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00		
REPLACE AND TIGHTEN CLIPS PER SIGN		EACH	1.00		
FURNISH AND INSTALL TRUSS DAMPER		EACH	1.00		
FURNISH AND INSTALL METAL SCREEN		EACH	1.00		
FURNISH AND INSTALL SADDLE BLOCK		EACH	4.00		
REMOVE LUMINAIRE		EACH	2.00		
DISCONNECT AND RECONNECT ELECTRIC SERVICE		EACH	1.00		
RELOCATE ELECTRIC SERVICE		EACH	1.00		
FURNISH AND INSTALL SAFETY CHAIN		EACH	2.00		
REMOVE AND REINSTALL WALKWAY		FOOT	18.50		
REMOVE EXISTING SIGN PANEL		EACH	1.00		

Location No.	4-05	State I.D. No.	4S072H74L001.6		
County	PEORIA	Route	I-474	M.P.	1.60
Direction	WB	Unit	Quantity		
Description of Work					
REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER SIGN		EACH	1.00		
TIGHTEN U-BOLT		EACH	3.00		
REPLACE HAND-HOLE COVER BOLT		EACH	2.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	10.00		
PAINT OVERHEAD SIGN SUPPORT		EACH	4.00		
FURNISH AND ERECT SIGN PANEL		SQ FT	625.75		
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STR		EACH	4.00		
REMOVE AND REERECT OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
REMOVE AND REERECT OVERHEAD SIGN END SUPPORT		EACH	2.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
FURNISH AND INSTALL SAFETY CHAIN		EACH	2.00		
FURNISH AND INSTALL WALKWAY/TIE DOWN BOLTS		EACH	1.00		
REMOVE LUMINAIRE		EACH	4.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		

Location No.	4-08	State I.D. No.	4S072S006L001.0		
County	PEORIA	Route	IL 6	M.P.	1.00
Direction	SB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	357.00		
REMOVE EXISTING SIGN PANEL		EACH	2.00		

Location No.	4-11	State I.D. No.	4C072H74L000.60		
County	PEORIA	Route	I-474	M.P.	0.60
Direction	WB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	575.50		
REMOVE EXISTING SIGN PANEL		EACH	3.00		

Location No.	4-03	State I.D. No.	4S048U074R045.30		
County	KNOX	Route	I-74	M.P.	45.3
Direction	EB	Unit	Quantity		
Description of Work					
REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER SIGN		EACH	2.00		
REPLACE U-BOLTS		EACH	3.00		
REPLACE HAND-HOLE COVER BOLT		EACH	2.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	10.00		
PAINT OVERHEAD SIGN SUPPORT		EACH	4.00		
FURNISH AND ERECT SIGN PANEL		SQ FT	299.00		
DISCONNECT AND RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE LUMINAIRE		EACH	3.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		
FURNISH AND INSTALL SAFETY CHAIN		EACH	2.00		

Location No.	4-06	State I.D. No.	4C072H74R000.10		
County	PEORIA	Route	I-474	M.P.	0.10
Direction	EB	Unit	Quantity		
Description of Work					
TIGHTEN CANTILEVER CONNECTION		EACH	1.00		
REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER SIGN		EACH	1.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	4.00		
PAINT OVERHEAD SIGN SUPPORT		EACH	4.00		
FURNISH AND ERECT SIGN PANEL		SQ FT	125.00		
FURNISH AND INSTALL SAFETY CHAIN		EACH	2.00		
REMOVE LUMINAIRE		EACH	4.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		

Location No.	4-09	State I.D. No.	GROUND MOUNT		
County	PEORIA	Route	IL 6	M.P.	1.5
Direction	SB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	306.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		

Location No.	4-12	State I.D. No.	GROUND MOUNT		
County	PEORIA	Route	I-474	M.P.	2.63
Direction	WB	Unit	Quantity		
Description of Work					
FURNISH AND ERECT SIGN PANEL		SQ FT	441.00		
REMOVE EXISTING SIGN PANEL		EACH	1.00		

FILE NAME = D4 Contract 46152 (12)2.dgn

USER NAME = hachem
 PLOT SCALE = 1/4" = 1'-0"
 PLOT DATE = 12/17/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

District 4
 Schedule of Truss Repair & Replacement

SCALE: SHEET NO. 4 OF 30 SHEETS STA. TO STA.

P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Various	D-4 OVD SIGN STR REPL II-28	KNOX-PEORIA	30	4
CONTRACT NO. 46152			ILLINOIS FED. AID PROJECT	