


STA.	OFFSET	EACH
608+88.42, RT	66'	1
609+16.46, RT	39'	1
610+59.27, RT	57'	1
611+81.59, RT	56'	1
612+65.48, RT	56'	1
613+31.30, LT	62'	1

- CLASS D PATCHES
- EXCAVATION - SPECIAL
- REMOVE AND REPLACE SIDEWALK
- SCARIFY EXISTING SURFACE
- PAVEMENT REMOVAL
- PRECAST CONCRETE PARKING BLOCK



CONTROL POINT #205
 STA. 613+69.03, 14.08" RT.
 N 1379179.85
 E 2124667.24
 ELEV.= 688.35

SIDEWALK REMOVAL
 LT STA. 608+50 - 608+53, 6 SQ FT

STA. 608+42.79, 7.31' LT.
 35' R

4" AGGREGATE
 14' WIDTH

MATCHLINE 607+25

P.C.C. SIDEWALK, 5"
 STA. 609+53 TO STA. 609+59 RT, 25.0 SQ. FT.

PAVEMENT REMOVAL
 STA. 607+25 TO STA. 607+30 RT, 0.6 SQ. YD.
 STA. 607+25 TO STA. 607+30 LT, 0.6 SQ. YD.

P.C.C. SIDEWALK, 5"
 STA. 608+45 TO STA. 608+55 RT, 45.0 SQ. FT.

SIDEWALK REMOVAL
 STA. 608+45 TO STA. 608+55 RT, 45.0 SQ. FT.

CLASS D PATCHES, TYPE IV, 10 INCH
 STA. 612+95.05 TO STA. 613+75, 160.0 SQ. YD.

SCARIFY EXISTING SURFACE
 STA. 607+25 TO STA. 612+95, 1442.3 SQ. YD.

REMOVE & RE-ERECT EXISTING SIGN
 STA 613+20 LT., 1 EACH

MATCH CONCRETE
 SURFACE ELEVATIONS

2"-0"
 TAPER
 20'

MATCHLINE 613+75

LOCATION	EXCAVATION SPECIAL
PARKING LOT STA. 609+00 TO STA. 609+75	(CU YD) 6.7
CAMPER PAD STA. 608+89 TO STA. 609+25.5 RT.	37.3
CAMPER PAD STA. 609+96 TO STA. 610+16 RT.	29.7
CAMPER PAD STA. 610+79 TO STA. 611+04 RT.	29.4
CAMPER PAD STA. 611+95 TO STA. 612+30 RT.	29.6
CAMPER PAD STA. 612+77 TO STA. 613+14 RT.	29.5
CAMPER PAD STA. 613+42 TO STA. 613+75 LT.	29.5

EXIST. CURVE C127
 PI STA. = 609+86.54
 $\Delta = 91^\circ 47' 46''$ (RT)
 D = 88° 08' 50"
 R = 65.00'
 T = 67.07'
 L = 104.14'
 E = 28.40'
 P.C. STA. = 609+19.47
 P.T. STA. = 610+23.61

EXIST. CURVE C128
 PI STA. = 611+36.86
 $\Delta = 41^\circ 22' 03''$ (LT)
 D = 45° 50' 12"
 R = 125.00'
 T = 47.19'
 L = 90.25'
 E = 8.61'
 P.C. STA. = 610+89.67
 P.T. STA. = 611+79.92

FILE NAME =
 #FILEL#

USER NAME = #USER#
 PLOT SCALE = #SCALE#
 PLOT DATE = #DATE#

DESIGNED - R.H.D.
 DRAWN - J.T.T.
 CHECKED - T.T.P.
 DATE - 12/09/10

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ARGYLE LAKE STATE PARK
 SIDE ROAD

SCALE: 1" = 20'
 SHEET NO. 87 OF 162 SHEETS
 STA. 607+25 TO STA. 613+75

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	ARGYLE LAKE STATE PARK	MCDONOUGH	162	87
CONTRACT NO. 46158				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				