

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0004	BRIDGE 0011	0004
20200100	EARTH EXCAVATION	CU YD	527	527		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	868	868		
20300100	CHANNEL EXCAVATION	CU YD	1257	1257		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	3720	3720		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	345	345		
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	3628			3628
25000310	SEEDING, CLASS 4	ACRE	0.8			0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72			72
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72			72
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72			72
25100115	MULCH, METHOD 2	ACRE	0.8	0.8		
25100630	EROSION CONTROL BLANKET	SQ YD	3628	3628		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80		
28000305	TEMPORARY DITCH CHECKS	FOOT	153	153		
28000400	PERIMETER EROSION BARRIER	FOOT	2889	2889		
28000510	INLET FILTERS	EACH	2	2		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1414		1414	
28200200	FILTER FABRIC	SQ YD	1414		1414	
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	4	4		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5		
40600300	AGGREGATE (PRIME COAT)	TON	25	25		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	57	57		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	24	24		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	17	17		

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0004	BRIDGE 0011	0004
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	453	453		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	302	302		
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	2416	2416		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	134	134		
44000100	PAVEMENT REMOVAL	SQ YD	4246	4246		
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	128	128		
44004250	PAVED SHOULDER REMOVAL	SQ YD	1835	1835		
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	27	27		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	41	41		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	60	60		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1515	1515		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2921	2921		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	500		500	
50300225	CONCRETE STRUCTURES	CU YD	212.4		212.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	377.9		377.9	
50300260	BRIDGE DECK GROOVING	SQ YD	1020		1020	
50300280	CONCRETE ENCASEMENT	CU YD	11.3		11.3	
50300300	PROTECTIVE COAT	SQ YD	1177		1177	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	3927		3927	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	114720		114720	
50800515	BAR SPLICERS	EACH	891		891	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1130		1130	
51202305	DRIVING PILES	FOOT	1130		1130	

LOCO INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, SLV	REVISED -
DATE - 12/30/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL ROUTE 23 OVER COON CREEK**

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. 88+00 TO STA. 103+55

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	24 B-2	MCHENRY	76	3
D-91-178-09		CONTRACT NO. 60F64		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		