

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0004	BRIDGE 0011	LANDSCAPING 0004
51203600	TEST PILE STEEL HPI2X53	EACH	4		4	
51204650	PILE SHOES	EACH	32		32	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	56		56	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	72		72	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2		
60107600	PIPE UNDERDRAINS, 4"	FOOT	68	68		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	50	50		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1531	1531		
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	28	28		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	1186	1186		
67000400	ENGINEER FIELD OFFICE, TYPE A	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1200	1200		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1200	1200		
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	7985	7985		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	816	816		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	50	50		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6		6	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	62	62		

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0004	BRIDGE 0011	LANDSCAPING 0004
* 78200510	BARRIER WALL MARKERS, TYPE A	EACH	49	49		
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	74	74		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2934	2934		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	56	50	6	
X0326276	TEMPORARY LIGHTING FOR SINGLE LANE STAGING	L SUM	1	1		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	164		164	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2157	2157		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1	
X7030300	WET REFLECTIVE TEMPORARY PAVEMENT MARKING TAPE, TYPE III	FOOT	6871	6871		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2416	2416		
Z0004552	APPROACH SLAB REMOVAL	SQ YD	107		107	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0026407	TEMPORARY SHEET PILING	SQ FT	1164		1164	
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	206	206		
X0322919	CLEAN EXISTING STRUCTURES	EACH	1	1		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	109	109		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	160		160	

**LOCO INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY  
DRAWN - ST, TSC  
CHECKED - MJY, SLV  
DATE - 12/30/2010

REVISED  
REVISED  
REVISED  
REVISED

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL ROUTE 23 OVER COON CREEK**

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. 88+00 TO STA. 103+55

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	24 B-2	MCHENRY	76	4
D-91-178-09			CONTRACT NO. 60F64	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

Rev