

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY ACIM	ROADWAY ACIM	SIGNING ACCMI		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY ACIM					
				0005	0014	0021						0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	453	453				*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	437	437					
40600300	AGGREGATE (PRIME COAT)	TON	2060	2060				*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1424673	1424673					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	309	309				*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	540	540					
40600895	CONSTRUCTING TEST STRIP	EACH	5	5				*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	41879	41879					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1917	1917				*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	14553	14553					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	941	941				*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	75	75					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	46016	46016				*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	62166	62166					
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	60947	60947				*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	120059	120059					
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	60947	60947				*78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	56049	56049					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	42102	42102				*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	56000	56000					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	146639	146639				*78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	6626	6626					
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SO YD	354572	354572				*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	2370	2370					
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	528321	528321				*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2500	2500					
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SO YD	5600	5600				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1500	1500					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	10	10				*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3200	3200					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	2500	2500				*88600600	DETECTOR LOOP REPLACEMENT	FOOT	117	117					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	800	800				89502380	REMOVE EXISTING HANDHOLE	EACH	2	2					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	2300	2300				X2020110	GRADING AND SHAPING SHOULDERS	UNIT	2183	2183					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	8730	8730				X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6344	6344					
58700300	CONCRETE SEALER	SO FT	749015		749015			X7010240	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	50	50					
64200105	SHOULDER RUMBLE STRIPS	FOOT	256143	256143				X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	2797346	2797346					
67100100	MOBILIZATION	L SUM	1	1				X7030035	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH	FOOT	96000	96000					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20				X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	1080	1080					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	35000	35000				X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	53600	53600					
*72000200	SIGN PANEL - TYPE 2	SO FT	570			570		X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	150	150					
*72000300	SIGN PANEL - TYPE 3	SO FT	673			673		*X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	7400	7400					
*72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2015			2015											
*72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	330			330											
*73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	16			16											
*73400100	CONCRETE FOUNDATIONS	CU YD	4			4											

* SPECIALITY ITEMS

Rev.

FILE NAME =	USER NAME = qureshlyo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\work\p\m\p\qureshlyo\087440\011310-str-plan.dwg		DRAWN -	REVISED -									55	.	COOK	197	3
PLOT SCALE = 52.9406" / IN.		CHECKED -	REVISED -									CONTRACT NO. 60164				
PLOT DATE = 1/3/2011		DATE -	REVISED -									SCALE:	SHEET NO.	OF	SHEETS	STA.