

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX, STATE STD, GEN NOTES
- 3-4 SUMMARY OF QUANTITIES
- 5 SCHEDULE OF QUANTITIES
- 6-7 TYPICAL SECTIONS
- 8 ALIGNMENT AND TIES
- 9 ROADWAY PLAN (PLAN AND PROFILE)
- 10 MOT GENERAL NOTES & CONSTRUCTION SEQUENCING
- 11 MOT TYPICAL SECTIONS
- 12 SUGGESTED STAGE OF CONSTRUCTION & TRAFFIC CONTROL - STAGE 1
- 13 SUGGESTED STAGE OF CONSTRUCTION & TRAFFIC CONTROL - STAGE 2
- 14 SUGGESTED STAGE OF CONSTRUCTION & TRAFFIC CONTROL - STAGE 3
- 15 SUGGESTED STAGE OF CONSTRUCTION & TRAFFIC CONTROL - STAGE 4
- 16 SUGGESTED STAGE OF CONSTRUCTION & TRAFFIC CONTROL - STAGE 5
- 17 EROSION CONTROL PLANS
- 18 DRAINAGE AND UTILITY PLAN
- 19 PAVEMENT MARKING & LANDSCAPING
- 20-25 DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS
- 26 TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN
- 27 TEMPORARY CABLE PLAN, TEMPORARY PHASE DESIGNATION DIAGRAM, SCHEDULE OF QUANTITIES
- 28 TEMPORARY LIGHTING FOR SINGLE LANE STAGING
- 29 GENERAL PLAN
- 30 STAGE CONSTRUCTION DETAILS
- 31 TEMPORARY CONCRETE BARRIER
- 32 GEOTEXTILE RETAINING WALL
- 33 FOUNDATION PLAN AND DETAILS
- 34 WINGWALL ELEVATIONS AND DETAILS
- 35 WINGWALL DETAILS
- 36 HEADWALL AND PARAPET DETAILS
- 37 BAR SPLICER ASSEMBLY DETAILS
- 38 METAL SHELL PILE DETAILS
- 39 GENERAL PLAN - RETAINING WALLS
- 40 SW & SE RETAINING WALLS
- 41 NE RETAINING WALL
- 42 RETAINING WALL DETAILS
- 43 BORING LOGS
- 44-53 CROSS SECTIONS
- 54 TC-10 DISTRICT ONE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS
- 55 TC-11 DISTRICT ONE TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS
- 56 TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS
- 57 TC-22 DISTRICT ONE ARTERIAL ROAD INFORMATION SIGN
- 58 BD-01 DRIVEWAY DETAILS - DISTANCE BETWEEN ROW AND FACE OF CURB & EDGE OF SHOULDER >= 15'
- 59-61 DISTRICT ONE STANDARD TEMPORARY LIGHTING AND TEMPORARY SIGNALS FOR SINGLE LANE STAGING

STATE STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 280001-05 TEMPORARY EROSION CONTROL SYSTEMS
- 602401-03 MANHOLE, TYPE A
- 602601-02 PRECAST REINFORCED CONCRETE FLAT SLAB TOP
- 602701-02 MANHOLE STEPS
- 604001-03 FRAME AND LIDS, TYPE 1
- 630001-09 STEEL PLATE BEAM GUARDRAIL
- 631031-09 TRAFFIC BARRIER TERMINAL, TYPE 6
- 701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY
- 701006-03 OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24' (600 mm) FROM PAVEMENT EDGE
- 701011-02 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
- 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY
- 701321-11 LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
- 701326-04 LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING FOR SPEEDS > 45MPH
- 701502-04 URBAN LANE CLOSURE WITH BIDIRECTIONAL LEFT TURN LANE
- 701901-01 TRAFFIC CONTROL DEVICES
- 704001-06 TEMPORARY CONCRETE BARRIER
- 780001-02 TYPICAL PAVEMENT MARKINGS

GENERAL NOTES:

1. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO VARIATIONS FOUND IN THE FIELD. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING MATERIALS. ANY ADJUSTMENTS PROPOSED BY THE CONTRACTOR MUST BE APPROVED BY THE ENGINEER. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE.
2. FORTY- EIGHT HOURS BEFORE STARTING EXCAVATION, THE CONTRACTOR WILL CALL J.U.L.I.E. (1-800-892-0123) OR 811 FOR LOCATIONS OF THE EXISTING UTILITIES.
3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
4. SAW CUTTING PRIOR TO ANY REMOVAL ITEMS NOTED ON THE PLANS OR DIRECTED BY THE ENGINEER SHALL BE CONSIDERED INCLUDED IN THE COST OF THE ITEMS BEING REMOVED.
5. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
6. THE CONTRACTOR SHALL USE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
7. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AS WELL AS ADJOINING RESIDENTIAL AREAS.
8. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, AS REQUIRED, PRIOR TO COMMENCING WITH CONSTRUCTION.
9. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO ASSURE THAT NO DEBRIS FALLS INTO THE WATERWAY. THE COST OF THIS WORK SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.
10. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
11. THE ENGINEER SHALL CONTACT DEBBIE HANLON, THE AREA TRAFFIC FIELD TECHNICIAN, AT (847) 715-8419 TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
12. ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OUTSIDE THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
13. UNLESS OTHERWISE NOTED ON THE PLANS ACCESS SHALL BE PROVIDED AT ALL TIMES TO PROPERTIES ABUTTING THE PROPOSED IMPROVEMENT. DRIVEWAYS WILL BE MAINTAINED USING "TEMPORARY ACCESS (PRIVATE/COMMERCIAL ENTRANCE)".
14. THE CONTRACTOR SHALL PREPARE IN-STREAM WORK PLANS (ALL COFFERDAMS, WORK PADS, AND EROSION AND SEDIMENT CONTROL, ETC.) AND SUBMIT TO THE ENGINEER AND THE U.S. ARMY CORP OF ENGINEERS FOR REVIEW AND APPROVAL. THE COST OF ALL IN-STREAM WORK ITEMS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

COMMITMENTS

NONE

PLAN	SURVEYED	DATE
	BY	
	PLOTTED	
	ALIGNED	
	CHECKED	
	FILED	
	CADD FILE NAME	
	NO.	

PLAN	SURVEYED	DATE
	BY	
	PLOTTED	
	ALIGNED	
	CHECKED	
	FILED	
	CADD FILE NAME	
	NO.	

...#D160J67-sht-gennotes.dgn
2/1/2011
2:13:42 PM



DESIGNED	REVISED - 2/10/2011
DRAWN	REVISED -
CHECKED	REVISED -
DATE	JANUARY 3, 2011
	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEET, STATE STANDARDS,
GENERAL NOTES AND COMMITMENTS

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1238	C-B-1	LAKE	62	2
CONTRACT NO. 60J67				
ILLINOIS FED. AID PROJECT				