

SUMMARY OF QUANTITIES

URBAN
1001 STATE

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	BRIDGE RECONSTRUCTION 0011	LANDSCAPING 0031
55101400	STORM SEWER REMOVAL 30"	FOOT	325	325		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	134		134	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60500040	REMOVING MANHOLES	EACH	1	1		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	112.5	112.5		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	504	504		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	107	107		
70104490	TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1	EACH	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4183	4183		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	263	263		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	238	238		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62	62		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3445	3445		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	24	24		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	19	19		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2220	2220		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	19	19		
Z0028462	GEOTEXTILE RETAINING WALL	SQ FT	130		130	
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	2878	2878		
X0326276	TEMPORARY LIGHTING FOR SINGLE LANE STAGING	L SUM	1	1		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	177		177	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6		
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	123	123		

* INDICATES SPECIALTY ITEMS

LETTERS AND SYMBOLS

URBAN
1001 STATE

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	BRIDGE RECONSTRUCTION 0011	LANDSCAPING 0031
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	19804	19804		
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	68	68		
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1		
XZ030256	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
XZ030260	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3449	3449		
Z0026407	TEMPORARY SHEET PILING	SQ FT	1004		1004	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100		
* A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2		2	
* A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	1		1	
* A2064012	TREE, QUERCUS ALBA X ROBUR CRIMSCHMIDT (CRIMSON SPIRE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2		2	
* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	28		28	
* B2006069	TREE, SYRINGA PEKINENSIS 'ZHING ZHIMING' (BEIJING GOLD PEKING LILAC), 7' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3		3	
Z0038140	THREE-SIDED PRECAST CONCRETE STRUCTURES 32'X10'	FOOT	51.2		51.2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		

* INDICATES SPECIALTY ITEMS

DATE: _____
BY: _____
SURVEYED: _____
ALIGNMENT CHECKED: _____
NOTE BOOK NO. _____
RT. OF WAY CHECKED: _____
PAID FILE NAME: _____

DATE: _____
BY: _____
SURVEYED: _____
ALIGNMENT CHECKED: _____
NOTE BOOK NO. _____
RT. OF WAY CHECKED: _____
PAID FILE NAME: _____

...D160J67-shf-S002.dgn
12/23/2010
10:04:17 AM



DESIGNED JRB
DRAWN JRB
CHECKED RJD
DATE JANUARY 3, 2011

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 176 OVER EAST SKOKIE DITCH
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.U. RTE. 1238	SECTION C-B-1	COUNTY LAKE	TOTAL SHEETS 61	SHEET NO. 4
CONTRACT NO. 60J67				
ILLINOIS FED. AID PROJECT				

Rev.