

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN 90% FED. 10% STATE TOTAL	IM DUPAGE COUNTY	IM COOK COUNTY	CMI SIGNAGE DUPAGE CO.	CODE NO	ITEM	UNIT	URBAN 90% FED. 10% STATE TOTAL	IM DUPAGE COUNTY	IM COOK COUNTY	CMI SIGNAGE DUPAGE CO.
			QUANTITIES	0005	0005	0021				QUANTITIES	0005	0005	0021
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	10		10			* 81000600	CONDUIT IN TRENCH, 2" DIA. GALVANIZED STEEL	FOOT	140	140	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	113	109	4			* 81900200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	140	140	
40600300	AGGREGATE (PRIME COAT)	TON	535	518	17			* 89502300	REMOVE ELECTRICAL CABLE FROM THE CONDUIT	FOOT	1580	1580	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	207	200	7			* 89502380	REMOVE EXISTING HANDHOLE	EACH	14	14	
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.75	0.25			* X0322727	POLYETHYLENE DUCT 1 1/4"	FOOT	140	140	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	15425	14935	490			X0326819	CONCRETE BARRIER REMOVAL AND REPLACEMENT DOUBLE FACE	FOOT	262	262	
42001300	PROTECTIVE COAT	SQ YD	130	130				X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAY)	L SUM	1	0.75	0.25
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	133705	129460	4245			Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	45	35	10
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1604	1554	50			Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	2408	2331	77			Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	4012	3885	127			* Z0033092	ELECTRIC CABLE IN CONDUIT NO. 18 4/C TWISTED, SHIELDED	FOOT	4000	4000	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	20		20			* X8130112	JUNCTION BOX TYPE J	EACH	14	14	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	68	48	20			Z0201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	42.7	42.7	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	32	24	8			44004250	PAVED SHOULDER REMOVAL	SQ YD	50	50	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	203	185	18			31101100	SUB BASE GRANULAR MATERIAL, TYPE B	CU YD	42.7	42.7	
63700900	CONCRETE BARRIER BASE	FOOT	212	212				X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	1	1	
64200105	SHOULDER RUMBLE STRIPS	FOOT	43019	41429	1590			Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	20	20	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	5	2			Z0001905	STRUCTURAL STEEL REPAIR	POUND	640	640	
67100100	MOBILIZATION	L SUM	1	0.75	0.25			X0321962	CONNECTION OF EXISTING PIPE UNDERDRAIN	EACH	1	1	
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	73745	71020	2725								
70300560	PAVEMENT MARKING TAPE TYPE III, 12"	FOOT	3405	3310	95								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	27988	26984	1004								
70400100	TEMPORARY CONCRETE BARRIER	FOOT	150	150									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	150	150									
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	73745	71020	2725								
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3405	3310	95								
*72000200	SIGN PANEL, TYPE 2	SQ FT	560			560							
*72000300	SIGN PANEL, TYPE 3	SQ FT	171			171							
*72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	120			120							
*73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	12			12							
*73304000	OVERHEAD SIGN STRUCTURE- BRIDGE MOUNTED	FOOT	13			13							
*78200520	BARRIER WALL MARKERS, TYPE B	EACH	8	8									
*81900200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	140	140									

* SPECIALTY ITEMS
Δ = Non-participating

Δ Rev. 7-25-11

Rev