

LOCATION					POLYMERIZED HMA SURFACE COURSE, SMA, N80	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL-19.0, N70	HMA SURFACE REMOVAL 2" (SEE NOTE 1)	HMA SURFACE REMOVAL 4"	SHOULDER RUMBLE STRIP	TEMPORARY PAVEMENT (INTERSTATE) (SEE NOTE 1)	PAVEMENT REMOVAL (SEE NOTE 1)
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(FOOT)	(SQ YD)	(SQ YD)
I-80	EB	MAINLINE	88+58.91	95+00.00	273.57	273.57	42.14	70.23	0.00	2944.23	641.09	0.00	0
I-80	EB	MAINLINE	95+00.00	110+00.00	576.81	576.81	143.60	239.33	0.00	6859.59	2652.00	0.00	0
I-80	EB	MAINLINE	110+00.00	125+00.00	598.64	598.64	143.55	239.24	0.00	7053.87	3000.00	0.00	0
I-80	EB	MAINLINE	125+00.00	140+00.00	609.87	609.87	132.79	221.32	0.00	7026.14	3000.00	0.00	0
I-80	EB	MAINLINE	140+00.00	155+00.00	591.80	591.80	121.54	202.56	0.00	6730.83	3000.00	0.00	0
I-80	EB	MAINLINE	155+00.00	170+00.00	594.78	594.78	118.91	198.19	0.00	6726.18	3000.00	0.00	0
I-80	EB	MAINLINE	170+00.00	185+00.00	591.94	591.94	154.87	258.12	0.00	7128.95	3000.00	0.00	0
I-80	EB	MAINLINE	185+00.00	200+00.00	589.32	589.32	148.37	247.29	0.00	7028.12	3000.00	0.00	0
I-80	EB	MAINLINE	200+00.00	215+00.00	582.08	582.08	140.98	234.96	0.00	6875.48	3000.00	0.00	0
I-80	EB	MAINLINE	215+00.00	230+00.00	583.45	583.45	147.12	245.19	0.00	6960.72	3000.00	0.00	0
I-80	EB	MAINLINE	230+00.00	245+00.00	591.49	591.49	136.18	228.96	0.00	6902.31	3000.00	0.00	0
I-80	EB	MAINLINE	245+00.00	247+13.80	84.08	84.08	19.60	32.67	0.00	984.05	427.60	0.00	0
I-80	EB	MAINLINE	250+06.20	260+00.00	386.99	386.99	103.40	172.33	0.00	4686.16	1987.60	0.00	0
I-80	EB	MAINLINE	260+00.00	269+36.65	417.33	417.33	123.53	99.33	570.81	4435.62	1392.35	0.00	0
I-80	EB	MAINLINE	269+65.81	275+00.00	203.83	203.83	84.67	86.74	291.32	2439.54	921.30	154.26	154.26
I-80	EB	MAINLINE	275+00.00	285+04.56	430.54	430.54	152.56	135.55	635.99	4812.27	1797.42	0.00	0
I-80	EB	MAINLINE	288+26.23	290+00.00	96.57	96.57	20.60	13.53	111.44	958.88	173.77	0.00	0
I-80	EB	MAINLINE	290+00.00	305+00.00	633.07	633.07	205.32	181.98	858.37	6952.23	2272.99	0.00	0
I-80	EB	MAINLINE	305+00.00	316+63.83	570.25	570.25	144.80	108.40	712.17	5865.83	1380.71	0.00	0
I-80	EB	MAINLINE	317+66.40	320+00.00	85.74	85.74	25.22	22.98	102.08	929.63	467.20	0.00	0
I-80	EB	MAINLINE	320+00.00	335+00.00	575.55	575.55	210.59	224.65	91.82	6743.52	3000.00	0.00	0
I-80	EB	MAINLINE	335+00.00	357+23.60	802.47	802.47	186.78	311.30	0.00	9,388.53	4,447.20	0.00	0.00
I-80	EB	MAINLINE	397+44.40	398+66.40	47.82	47.82	10.25	17.08	0.00	549.00	244.00	0.00	0.00
I-80	EB	MAINLINE	398+66.40	419+00.00	733.90	733.90	170.82	284.70	0.00	8,586.31	4,067.20	0.00	0.00
I-80	EB	MAINLINE	419+00.00	449+00.00	1,082.67	1,082.67	252.00	420.00	0.00	12,666.67	6,000.00	0.00	0.00
I-80	EB	MAINLINE	449+00.00	479+00.00	1,024.05	1,024.05	238.36	397.26	0.00	11,980.94	5,675.18	0.00	0.00
I-80	EB	MAINLINE	479+00.00	500+58.80	779.09	779.09	181.34	302.23	0.00	9,114.93	4,317.60	0.00	0.00
I-80	EB	MAINLINE	500+58.80	504+82.80	215.02	215.02	27.70	46.17	0.00	2,226.00	424.00	0.00	0.00
I-80	EB	MAINLINE	504+82.80	505+00.00	6.21	6.21	0.98	1.63	0.00	67.08	17.20	0.00	0.00
I-80	EB	MAINLINE	505+00.00	517+26.70	442.70	442.70	126.61	211.02	0.00	5,459.97	2,060.16	0.00	0.00
I-80	EB	MAINLINE	517+26.70	520+35.50	176.77	176.77	25.94	43.23	0.00	1,887.11	308.80	0.00	0.00
I-80	EB	MAINLINE	520+35.50	521+95.30	92.47	92.47	13.42	22.37	0.00	985.43	159.80	0.00	0.00
LARKN-BB	EB	RAMP	2+49.55	3+08.29	12.43	12.43	4.93	8.22	0.00	169.69	0.00	0.00	0.00
I-80	EB	MAINLINE	521+95.30	531+71.10	352.16	352.16	106.53	177.55	0.00	4,412.49	1,566.47	0.00	0.00
I-80	EB	MAINLINE	531+71.10	533+00.00	78.04	78.04	8.42	14.04	0.00	797.03	128.90	0.00	0.00
I-80	EB	MAINLINE	533+00.00	541+74.10	414.98	414.98	57.11	95.18	0.00	4,385.07	1,748.20	0.00	0.00
I-80	EB	MAINLINE	541+74.10	544+48.53	99.04	99.04	23.05	38.42	0.00	1,158.70	548.86	0.00	0.00
<b>TOTAL</b>					16,028	16,028	3,955	5,852	3,374	184,879	75,828	154	154

**NOTES**  
1. FOR MAINTENANCE OF TRAFFIC (SEE MOT PLANS)