


FOR INFORMATION

ITEM	UNIT	ESTIMATED QUANTITIES		
SCUPPERS	EACH	4		
BRIDGE DRAINAGE SYSTEM	L. SUM	1		

COST OF FURNISHING AND INSTALLING DRAIN PIPE, FITTINGS, ELBOWS, PLATES
AND MOUNTING HARDWARE NECESSARY TO INSTALL THE BRIDGE DRAINAGE SYSTEM
SHALL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR BRIDGE DRAINAGE SYSTEM.

RTE. 0325 \*99-2 (K & HB-!-R) Face of Parapet -FEB. ROAD DIST. NO. ILLINOIS FED. AND PROJECT SHEET S-21 OF S-26 В –⊈ Scupper 2-#5 a4(E) bars 2'-0 Long at 4" cts. Top -(Typ.) (Sht. 5-4 & S-5)

## PLAN



## SECTION B-B

## NOTES:

ALL DRAIN PIPES AND FITTINGS SHALL BE FIBERGLASS CONFORMING TO ASTM D2996 RTRP OR ASTM D2997 RTRP WITH SHORT TERM RUPTURE STRENGTH HOOP TENSILE STRESS OF 30,000 PSI MINIMUM. THE SURFACE OF FIBREGLASS PIPE SHALL BE FREE OF BOND INHIBITING AGENTS.

ALL PIPE HANGERS, SUPPORTS AND HARDWARE SHALL BE GALVANIZED BY THE HOT-DIP PROCESS. THE ZINC COATING SHALL CONFORM TO THE REQUIREMENTS OF ASTM AIZ J.

ALL EXTERIOR SURFACES OF THE FLOOR DRAINS SHALL BE PAINTED WITH THE INTERWEDIATE COAT AND TOP COAT SPECIFIED FOR STRUCTURAL STEEL IN SECTION 509 OF THE STANDARD SPECIFICATIONS EXCEPT THAT THE COLOR SHALL BE MUNSELL NO. 7.5 G4/B INTERSTATE GREEN.
FIBERGLASS TO HAVE PREWASH AS PER MIL-P-15328 B PRIOR TO PAINTING.

PIPE HANGERS SHALL BE PROVIDED ON ALL HORIZONTAL PIPES AT EACH TEE, ELBOW, OR CHANGE IN DIRECTION AND AT INTERMEDIATE POINTS NOT MORE THAN 5'-0" ON CENTERS.

THE CONTRACTOR MAY USE ALTERNATE PIPE HANGERS. THE PIPE HANGERS SHALL HAVE A LOAD CAPACITY OF NOT LESS THAN 500 LBS. AND SHALL BE DESIGNED SO AS NOT TO APPLY EXCESSIVE COMPRESSIVE STRESS TO THE PIPE. ALTERNATE PIPE HANGER DESIGNS MUST BE APPROVED BY THE

DRAINS SHALL BE LOCATED CLEAR OF ALL CROSS FRAMES.

WORK THIS SHEET WITH SHT. S-1, S-4, S-5, S-22, S-23 & R-35

		DECK DRAINAGE DETAILS
REVISI	ONS	STATE OF ILLINOIS
NAME	DATE	DEPARTMENT OF TRANSPORTATION
		SECTION 99-2 (K & HB-1-R)
		FAI-SC OVER HOUBOLT RD. (FAU-G325)
		SN 699-0301 E.B. AND 699-0302 W.B.
		Phase II
		MILL COUNTY

DESIGNED - DF REVISED REVISED USER NAME = Imuelle DRAWN - LAM CHECKED - BLU REVISED DATE 01/19/2011 REVISED PLOT DATE = 1/17/2011 4:44:03 PM

FLUOR DANIEL 9

DETAIL OF EXPANSION COLLAR



STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**  FOR INFORMATION ONLY - EXISTING DRAINAGE SYSTEM DETAILS WESTBOUND FAI-80 OVER HOUBOLT ROAD STRUCTURE NO. 099-0302

 ·····										
F.A.I RTE.	RTE. SECTION					COUNTY TOTAL SHEET		AL TS	SHEE'	
80	80 99(3&4)RS-4						WILL	117		96
							CONTRACT	NO.	60	M65
FED.	ROAD	DIST.	NO.	ILLINOIS	FED.	ΑI	D PROJECT			