

RESURFACING SCHEDULE

LOCATION					POLYMERIZED HMA SURFACE COURSE, SMA, N80	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL-19.0, N70	HMA SURFACE REMOVAL, 2"	HMA SURFACE REMOVAL, 4"	SHOULDER RUMBLE STRIP
ALIGNMENT	DIRECTION	DESCRIPTION	STATION	STATION	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(FOOT)
I-80	WB	SHEET 1	544+48.53	563+00.00	619	619	233	240	796	2,708	3,431
I-80	WB	SHEET 2	563+00.00	569+41.30	231	231	86	90	285	2,708	1,283
I-80	WB	SHEET 2	569+41.30	570+64.90	53	53	15	15	55	587	124
I-80	WB	SHEET 2	570+64.90	577+49.35	392	392	99	89	413	3,977	441
I-80	WB	SHEET 2	577+49.35	578+00.00	11	11	5	3	23	186	51
I-80	WB	SHEET 3	578+00.00	579+49.70	54	54	22	25	67	659	150
I-80	WB	SHEET 3	579+49.70	593+00.00	406	406	141	167	364	4,788	2,235
RAYNR-D	WB	SHEET 3	23+99.00	21+26.53	64	64	27	45	0	949	0
I-80	WB	SHEET 4	593+00.00	601+59.27	310	310	164	194	383	4,158	1,345
RAYNR-C	WB	SHEET 4	0+00.00	3+06.40	88	88	23	38	0	1,055	0
I-80	WB	SHEET 5	607+00.00	622+00.00	0	0	0	0	0	0	0
I-80	WB	SHEET 6	622+00.00	626+04.10	0	0	0	0	0	0	0
I-80	WB	SHEET 6	626+04.10	635+83.29	619	619	165	151	665	6,601	1,559
CHICAGO-D	WB	SHEET 6	10+32.45	18+51.45	158	158	124	206	0	2,882	0
CHICAGO-DD	WB	SHEET 6	2+47.33	5+88.01	67	67	53	88	0	1,223	0
I-80	WB	SHEET 7	637+61.10	642+38.38	309	309	49	42	219	3,056	724
CHICAGO-CC	WB	SHEET 7	2+91.26	10+95.50	159	159	123	205	0	2,880	0
I-80	WB	SHEET 7	647+13.00	651+58.11	237	237	40	29	205	2,320	890
I-80	WB	SHEET 8	652+00.00	667+00.00	527	527	160	156	600	5,552	2,055
I-80	WB	SHEET 9	667+00.00	697+00.00	852	852	349	438	1,084	10,017	4,269
I-80	WB	SHEET 10	697+00.00	727+00.00	930	930	256	361	173	10,877	5,152
I-80	WB	SHEET 11	727+00.00	738+00.00	549	549	127	279	0	6,539	1,329
I-80	WB	SHEET 12	738+00.00	753+00.00	561	561	131	260	0	6,333	3,000
I-80	WB	SHEET 13	753+00.00	783+00.00	1,170	1,170	291	483	0	9,953	5,562
I-80	WB	SHEET 14	783+00.00	813+00.00	1,103	1,103	265	470	0	12,667	6,084
I-80	WB	SHEET 15	813+00.00	843+00.00	1,083	1,083	256	210	0	11,167	6,000
I-80	WB	SHEET 16	843+00.00	873+00.00	1,089	1,089	254	422	0	8,796	5,833
I-80	WB	SHEET 17	873+00.00	885+00.00	603	603	115	245	0	6,936	1,633
US 30 RAMP-B	WB	SHEET 18	201+52.79	211+00.00	189	189	123	213	0	3,208	0
US 30 RAMP-D	WB	SHEET 18	105+99.88	113+44.08	148	148	95	182	0	2,624	0
US 30 RAMPS-B & D	WB	SHEET 18	RAMP END		109	109	18	0	0	970	0
TOTAL					12,688	12,688	3,808	5,345	5,332	136,376	53,147

TEMPORARY INFORMATION SIGNING - STAGE 1

STATION	LEGEND / DESCRIPTION	PANEL COVER DIMENSIONS		PANEL COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
600+91	EXIT ONLY TO BE COVERED WITH SINGLE ARROW	20	2	48
N/A	ADVANCED WARNING SIGNING - "EXPECT DELAYS"	14	10	133
N/A	ADVANCED WARNING SIGNING - "EXPECT DELAYS"	14	10	133
N/A	ADVANCED WARNING SIGNING - "EXPECT DELAYS"	14	10	133
613+35	RIGHT 1000 FEET	3	20	50
613+35	EXIT ARROW TO BE COVERED	3	2	5
TOTAL				507

TEMPORARY INFORMATION SIGNING - STAGE 2

STATION	LEGEND / DESCRIPTION	PANEL COVER DIMENSIONS		PANEL COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
600+91	EXIT ONLY TO BE COVERED WITH SINGLE ARROW	20	2	48
613+35	RIGHT 1000 FEET	3	20	50
613+35	EXIT ARROW TO BE COVERED	3	2	5
613+35	EXIT ARROW TO BE COVERED	3	2	5
TOTAL				113

TEMPORARY PAVEMENT MARKING AND TEMPORARY IMPACT ATTENUATOR SCHEDULE

STAGE	PAVEMENT MARKING REMOVAL (SQFT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH (FOOT)	WET REFLECTIVE TEMPORARY TAPE LETTERS AND SYMBOLS (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 (EACH)
1	13,392	32,698	0	4,652	740	0	2	5	0
2	0	51,137	4,365	7,220	1,737	0	0	0	10
RESURFACING	0	161,396	16,702	8,259	128	146	0	0	0
TOTAL	13,392	245,231	21,087	20,131	2,604	146	2	5	10