

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY US 45/143RD	TRACK RELOCATION	LANDSCAPING		PLATFORM	VILLAGE OF ORLAND PARK	
				80% FED 20% STATE 0003	80% FED 20% STATE 0021	80% FED 20% STATE 0003		80% FED 20% STATE 0003	100% VOP 0043	
X0327153	CONDUIT ^{IN TRENCH} 1 1/2" DIA., GALVANIZED STEEL (FURNISH ONLY)	FOOT	1,350						1,350	
X0327154	HANDHOLE, PORTLAND CEMENT CONCRETE (FURNISH ONLY)	EACH	2						2	
X0327155	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10 (FURNISH ONLY)	FOOT	1,700						1,700	
X0327156	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8 (FURNISH ONLY)	FOOT	5,100						5,100	
X0327157	AERIAL CABLE, 3-1/C NO. 8 WITH MESSENGER WIRE (FURNISH ONLY)	FOOT	325						325	
X0327158	TRENCH AND BACKFILL FOR ELECTRICAL WORK (FURNISH ONLY)	FOOT	1,750						1,750	
X0327159	LIGHT POLE, WOOD, 20 FOOT, CLASS 5 (FURNISH ONLY)	EACH	1						1	
X0327160	LIGHT POLE, WOOD, 40 FOOT, CLASS 3 (FURNISH ONLY)	EACH	2						2	
X0327161	LIGHT POLE FOUNDATION, 30" DIAMETER (FURNISH ONLY)	FOOT	143						143	
X0327162	LIGHT POLE, SPECIAL (DECORATIVE ORNAMENTAL) (FURNISH ONLY)	EACH	12						12	
X0327163	LUMINAIRE (FURNISH ONLY)	EACH	12						12	
X0327164	HOT-MIX ASPHALT RAILROAD STATION PLATFORM (FURNISH ONLY)	SQ FT	12,845						12,845	
X0327165	CONCRETE RAILROAD STATION PLATFORM (FURNISH ONLY)	SQ FT	4,218						4,218	
X0327166	INTERTRACK WIRE FENCE (FURNISH ONLY)	FOOT	1,178						1,178	
X0327167	PEDESTRIAN CROSSWALK (FURNISH ONLY)	SQ FT	300						300	
X0327168	TEMPORARY PEDESTRIAN CROSSWALK (FURNISH ONLY)	SQ FT	300						300	
X0327169	TEMPORARY ISLAND BOARDING PLATFORM (FURNISH ONLY)	SQ FT	1,440						1,440	
XX003668	PRECONSTRUCTION VIDEOTAPING	L SUM	1							1

* DENOTES SPECIALTY ITEM
 VOP = VILLAGE OF ORLAND PARK

FILE NAME D:\62909-SHT-50005.dgn	USER NAME = TKluegel	DESIGNED - MJT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 330	SECTION 2010-135-I	COUNTY COOK	TOTAL SHEETS 101	SHEET NO. 8	
PLOT SCALE = 1:50	CHECKED - TRK	REVISED -	SCALE: N.T.S.			SHEET NO. 5 OF 5 SHEETS	STA. TO STA.	SQ-05		CONTRACT NO. 60N09	
PLOT DATE = 1/7/2011	DATE - 12/17/10	REVISED -	ILLINOIS FED. AID PROJECT								