

SUMMARY OF QUANTITIES

DATE	
BY	
SURVEY NO.	
DATE PLOTTED	
TEMPLATE	
AREAS CHECKED	

DATE	
BY	
SURVEY NO.	
DATE PLOTTED	
TEMPLATE	
AREAS CHECKED	

CODE NO.	SUMMARY OF QUANTITIES		UNIT	TOTAL	0028 ROADWAY
	PAY ITEM				
70400100		TEMPORARY CONCRETE BARRIER	FOOT	165	165
70400200		RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	165	165
78000200	^	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,797	3,797
78000300	^	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	3,797	3,797
78300100		PAVEMENT MARKING REMOVAL	SQ FT	2,726	2,726
80400100	^ *	ELECTRIC SERVICE INSTALLATION	EACH	1	1
80400200	^ *	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1
81000300	^	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	50	50
81000700	^	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	150	150
81200100	^	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	269	269
81300980	^	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8" X 8" X 6"	EACH	2	2
81702110	^	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,149	1,149
81702170	^	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2/0	FOOT	480	480
81900200	^ *	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	200	200
X2010350	*	TREE REMOVAL, ACRES (SPECIAL)	ACRE	1.1	1.1
X2070304	*	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,190	1,190
X2501800	* ^	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.5	0.5
X2800500	*	INLET PROTECTION, SPECIAL	EACH	4	4
X6013600	*	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	1,669	1,669
X6700405	*	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	7	7
X7010216	*	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X8250505	^ *	LIGHTING CONTROLLER, SPECIAL	EACH	1	1
XX005713	^ *	ORNAMENTAL RAILING	FOOT	145	145
XX006658	*	FLOCCULATION LOGS	EACH	20	20
XX006659	*	FLOCCULATION POWDER	POUND	10	10
XX006698	* ^	TREE PROTECTION AND PRESERVATION	EACH	30	30

CODE NO.	SUMMARY OF QUANTITIES		UNIT	TOTAL	0028 ROADWAY
	PAY ITEM				
XX007023	*	STAINING CONCRETE STRUCTURES	SQ YD	275	275
XX007797	^ *	LUMINAIRE (SPECIAL)	EACH	12	12
Z0001050	*	AGGREGATE SUBGRADE 12"	SQ YD	576	576
Z0013797	*	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	334	334
Z0019600	*	DUST CONTROL WATERING	UNIT	5	5
Z0022800	*	FENCE REMOVAL	FOOT	1,092	1,092
Z0030240	*	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Z0030340	*	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2
Z0030850	*	TEMPORARY INFORMATION SIGNING	SQ FT	77	77
Z0042002	*	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,976	3,976
Z0046306	*	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	410	410
Z0062456	*	TEMPORARY PAVEMENT	SQ YD	2,346	2,346
Z0073002	*	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2,207	2,207
Z0076600	^^ *	TRAINEES	HOUR	5.00	5.00

^ DENOTES SPECIALTY ITEM
 ^^ DENOTES CONSTRUCTION TYPE CODE 0042
 * DENOTES SPECIAL PROVISION