


SPECIALTY ITEM	SPECIAL PROVISION	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						RECONSTRUCTION, CAPACITY ADDED	0003
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
		60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	12		12
		60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	19		19
		60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2
		60221700	MANHOLES, TYPE A, 5'-DIAMETER, TY 8 GRATE	EACH	3		3
		60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	10		10
		60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
		60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME & GRATE	EACH	1		1
		60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	8		8
		60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	30		30
		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	2		2
		60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8		8
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4579		4,579
		60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	1173		1,173
		60624600	CORRUGATED MEDIAN	SQ FT	81		81
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
		67100100	MOBILIZATION	L SUM	1		1
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	28		28
		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	22663		22,663
		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	795		795
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11421		11,421
		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	16330		16,330
		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	250		250
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	400		400
+		78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	164		164
		78300100	PAVEMENT MARKING REMOVAL	SQ FT	1491		1,491
+		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	164		164
+		80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1
+		81000200	CONDUIT IN TRENCH, 3/4" DIA., GALVANIZED STEEL	FOOT	15		15
+		81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2105		2,105
+		81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	44		44
+		81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	739		739
+		81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	65		65

SPECIALTY ITEM	SPECIAL PROVISION	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
						RECONSTRUCTION, CAPACITY ADDED	0003
+		81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	79		79
+		81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2399		2,399
+		81400100	HANDHOLE	EACH	18		18
+		81400200	HEAVY-DUTY HANDHOLE	EACH	4		4
+		81400300	DOUBLE HANDHOLE	EACH	1		1
+		81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4653		4,653
+		81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	112		112
+		81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	61		61
+		81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	183		183
+		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5236		5,236
+		82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	20		20
+		82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4		4
+		82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100 AMP	EACH	1		1
+		83600200	LIGHT POLE FOUNDATION, .24" DIAMETER	FOOT	260		260
+		83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	20		20
+		84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1		1
+		84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1		1
+		84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1		1
+	DIST. 1	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3		3
+	DIST. 1	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1
+		86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1
+	DIST. 1	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2/C	FOOT	3168		3,168
+	DIST. 1	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3/C	FOOT	5650		5,650
+	DIST. 1	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5/C	FOOT	6778		6,778
+	DIST. 1	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7/C	FOOT	3234		3,234
+	DIST. 1	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	8440		8,440
+	DIST. 1	87301804	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 1C	FOOT	1960		1,960
+	DIST. 1	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	40		40
+	DIST. 1	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT	EACH	4		4
+		87704306	STEEL COMB. MAST ARM ASSEMBLY AND POLE WITH DUAL ARMS, 16 FT. AND 58 FT.	EACH	1		1
+		87704308	STEEL COMB. MAST ARM ASSEMBLY AND POLE WITH DUAL ARMS, 18 FT. AND 60 FT.	EACH	1		1
+		87704309	STEEL COMB. MAST ARM ASSEMBLY AND POLE WITH DUAL ARMS, 18 FT. AND 62 FT.	EACH	1		1
+		87704315	STEEL COMB. MAST ARM ASSEMBLY AND POLE WITH DUAL ARMS, 22 FT. AND 60 FT.	EACH	1		1
+	DIST. 1	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20		20

PROJECT SPECIFIC SPECIAL PROVISION  
DIST. 1 I.D.O.T. DISTRICT 1 SPECIAL PROVISION  
KDOT K.D.O.T. SPECIAL PROVISION



USER NAME = Matt Baldwin	DESIGNED - PWK	REVISED -
PLOT SCALE = 1:8000 1" = 80'	DRAWN - ERD	REVISED -
PLOT DATE = 2/7/2011	CHECKED - KDF	REVISED -
	DATE - 12/29/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	01-00269-00-CH	KANE	124	5
CONTRACT NO. 63533				
ILLINOIS FED. AID PROJECT				

FILE NAME = L:\VMECD\09292010\01-00269-00-CH\01-00269-00-CH.dgn