HOT–MIX ASPHALT SURFACE

	HMA SURFACE COURSE MIX "C" N50 (TON)
FROM PAVEMENT SCHEDULE	1,177
FROM DRIVEWAY SCHEDULE	308
TOTALS	1,485

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS

BEGIN STATION	END STATION	REMOVAL DISPOSAL UNSUITABLE MATERIALS (CU YD)
FOR PARKWAY RESTORATION		
GLEN OAKS DRIVE		
9+45	30+74	230
SUB-TOTAL		230
BRIARGATE DRIVE		
1+00	7+33	101
SUB-TOTAL		101
GLEN OAKS COURT		
1+00	2+74	16
SUB-TOTAL		16
VIVIAN DRIVE		
1+00	2+53	31
SUB-TOTAL		31
FROM PAVEMENT SCHEDULE		72
TOTALS		450

PAVEMENT

BEGIN STATION	END STATION	PAVEMENT AREA (SQ YD)	HMA SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)	HMA SURFACE REMOVAL, 1 1/2" (SQ YD)	HMA SURFACE REMOVAL, BUTT JOINT (SQ YD)	PREPARATION OF BASE (SQ YD)	AGGREGATE BASE COURSE, TYPE B (TON)	BASE REPAIRS: BASE COURSE REMOVAL (SPECIAL) (SQ YD)	BASE REPAIRS: AGGREGATE BASE COURSE, TYPE B (TON)	REMOVAL DISPOSAL UNSUITABLE MATERIALS (CU YD)	POROUS GRANULAR EMBANKMENT, SUBGRADE (CU YD)	HMA BINDER COURSE IL-19.0 N50 (TON)	HMA SURFACE COURSE MIX "C" N50 (TON)
GLEN OAKS DRIVE													
9+45	13+07	1,351	1,351	-	28	1,351	78	137	52	10	10	237	160
13+07	16+12	825	825	-	0	825	48	85	32	6	6	145	98
16+12	19+14	820	820	-	0	820	48	82	31	6	6	144	97
19+14	24+66.5	1,717	1,717	-	14	1,717	100	175	66	12	12	302	203
24+66.5	27+73	980	980	-	14	980	57	101	38	7	7	172	116
27+73	30+74	1,217	1,217	-	28	1,217	71	125	47	9	9	214	144
SUB-TOTAL		6,910	6,910	0	84	6,910	402	705	266	50	50	1,214	818
BRIARGATE DRIVE													
1+00	7+33	2,000	2,000	-	28	2,000	116	201	76	14	14	351	236
SUB-TOTAL		2,000	2,000	0	28	2,000	116	201	76	14	14	351	236
GLEN OAKS COURT													
1+00	2+74	660	660	-		660	39	67	25	6	6	116	78
SUB-TOTAL		660	660	0	0	660	39	67	25	6	6	116	78
VIVIAN DRIVE													
1+00	2+53	460	114	346	14	114	7	18	7	2	2	20	45
SUB-TOTAL		460	114	346	14	114	7	18	7	2	2	20	45
TOTALS		10,030	9,684	346	126	9,684	564	991	374	72	72	1,701	1,177

COPYRIGHT © 2010 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-00121 - EXPIRES 4/30/2011
USER:rcrmo 12/9/2010 5:03:53 PM
...\plot-cr-var\PDF22x34.plt
...\PLOTS\PH2.DWG(2.TS)
R:\CP361\SLSAN\CORE\C041B0\CADD-SURVEY\DRAWINGS\IDNS\041180-SOM.sht

BAXTER & WOODMAN Consulting Engineers

DESIGNED - MWP	REVISED - 12-01-10 IDOT REVIEW	
DRAWN - KAR	REVISED -	
CHECKED - RWL	REVISED -	
DATE - 10-01-10	FILE - 041180-SOM.sht	

CITY OF COUNTRY CLUB HILLS, ILLINOIS
GLEN OAKS DRIVE INFRASTRUCTURE IMPROVEMENTS

SCHEDULE OF QUANTITIES

SCALE: STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	04-00027-03-PV	COOK	36	11
	C-91-004-05	CONTRACT NO. 63539		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT HPD-897(008)		