

SUMMARY OF QUANTITIES

			URBAN	
			0040	
			80% FED 20% STATE	
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	
20100110	TREE REMOVAL (6 TO 15' DIAMETER UNITS)	UNIT	48	
20100210	TREE REMOVAL (OVER 15' DIAMETER UNITS)	UNIT	54	
20200100	EARTH EXCAVATION	CU YD	110	
20200200	ROCK EXCAVATION	CU YD	22	
* 25100630	EROSION CONTROL BLANKET	SQ YD	438	
* 25200110	SODDING, SALT TOLERANT	SQ YD	278	
* 25200200	SUPPLEMENTAL WATERING	UNIT	13	
28000305	TEMPORARY DITCH CHECKS	FOOT	20	
28000400	PERIMETER EROSION BARRIER	FOOT	171	
28000500	INLET ^{AND} PIPE PROTECTION	EACH	1	
28100107	STONE RIPRAP, CLASS A4	SQ YD	147	
28200200	FILTER FABRIC	SQ YD	470	
28400100	GABIONS	CU YD	288	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX"D", N50	TON	71	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	56	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	214	
44000400	GUTTER REMOVAL	FOOT	49	
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	155	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	32	
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	EACH	1	
50200100	STRUCTURE EXCAVATION	CU YD	260	

* SPECIALTY ITEMS