

SCHEDULE OF QUANTITIES

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	(6 Applications x 100 lbs / acre)					
US BUS 20							
660	Sta 120 + 20	-	139	+	51.5	LT	
180	Sta 120 + 20	-	126	+	41	RT	
480	Sta 128 + 00	-	139	+	51.5	RT	
ANDERSON DRIVE							
60	Sta 47 + 75	-	49	+	50	LT	
60	Sta 47 + 75	-	49	+	50	RT	
<u>1,440 TOTAL</u>							

28000305 TEMPORARY DITCH CHECKS

FOOT	LOCATION				
US BUS 20					
10	Sta 120 + 50				RT
10	Sta 122 + 00				RT
10	Sta 123 + 50				RT
10	Sta 126 + 50				RT
10	Sta 130 + 00				RT
10	Sta 131 + 05				RT
10	Sta 131 + 15				RT
10	Sta 131 + 50				RT
10	Sta 133 + 50				RT
10	Sta 134 + 15				RT
10	Sta 135 + 50				RT
10	Sta 136 + 50				RT
10	Sta 137 + 50				RT
10	Sta 138 + 50				RT
10	Sta 120 + 50				LT
10	Sta 122 + 50				LT
10	Sta 127 + 00				LT
10	Sta 129 + 00				LT
10	Sta 131 + 00				LT
10	Sta 131 + 15				LT
10	Sta 132 + 25				LT
10	Sta 135 + 00				LT
10	Sta 136 + 00				LT
10	Sta 137 + 00				LT
10	Sta 138 + 00				LT
10	Sta 139 + 00				LT
ANDERSON DRIVE					
10	Sta 47 + 25				RT
10	Sta 47 + 50				RT
10	Sta 48 + 00				RT
10	Sta 49 + 00				RT
10	Sta 49 + 50				RT
10	Sta 47 + 25				LT
10	Sta 47 + 75				LT
10	Sta 48 + 50				LT
10	Sta 49 + 00				LT
10	Sta 49 + 50				LT
<u>360 TOTAL</u>					

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION					
US BUS 20						
200	Sta 122 + 25	-	124	+	25	RT
250	Sta 124 + 75	-	127	+	25	RT
230	Sta 128 + 75	-	131	+	5	RT
210	Sta 131 + 15	-	133	+	25	RT
<u>890 TOTAL</u>						

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION				
US BUS 20					
1	Sta 121 + 64				CE - RT
1	Sta 129 + 39				PE - LT
1	Sta 131 + 09.5				Culvert - LT
1	Sta 131 + 21				18" Pipe Inlet - RT
1	Sta 132 + 10				PE - LT
1	Sta 136 + 27				PE - LT
ANDERSON DRIVE					
1	Sta 48 + 53				CE - LT
1	Sta 48 + 92				CE - RT
<u>8 TOTAL</u>					

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION					
US BUS 20						
66.7	Sta 120 + 20	-	120	+	45	(24' x 25')
67.2	Sta 139 + 26.5	-	139	+	51.5	(24.2' x 25')
ANDERSON DRIVE						
67.8	Sta 47 + 00	-	47	+	25	(24.4' x 25')
<u>201.7 TOTAL</u>						

40600990 TEMPORARY RAMP

SQ YD	LOCATION				
US BUS 20					
20.0	Sta 120 + 20				(24' x 7.5')
20.2	Sta 139 + 51.5				(24.2' x 7.5')
ANDERSON DRIVE					
20.3	Sta 47 + 00				(24.4' x 7.5')
<u>60.5 TOTAL</u>					

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION					
US BUS 20						
650.8	Sta 120 + 20	-	139	+	51.5	LT
249.9	Sta 120 + 20	-	127	+	10.6	RT
382.1	Sta 128 + 18.4	-	139	+	51.5	RT
<u>1,282.8 TOTAL</u>						

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION					
US BUS 20						
1,744.5	Sta 121 + 32	-	138	+	76.5	Widening LT
530.0	Sta 121 + 73	-	127	+	03	Widening RT
ANDERSON DRIVE						
156.0	Sta 48 + 62	-	49	+	86	Widening LT with Return
152.5	Sta 49 + 27	-	49	+	90	Widening RT with Return
<u>2,583.0 TOTAL</u>						