

SUMMARY OF QUANTITIES

URBAN
100% State
0014

Pay Item	Description	Unit	Quantity
40600990	TEMPORARY RAMP	SQ YD	18
42001300	PROTECTIVE COAT	SQ YD	42.8
44000300	CURB REMOVAL	FOOT	260
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	1170
50157300	PROTECTIVE SHIELD	SQ YD	5871
50102400	CONCRETE REMOVAL	CU YD	15.3
50300100	FLOOR DRAINS	EACH	64
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.3
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1580
50800515	BAR SPLICERS	EACH	22
52000050	PREFORMED JOINT SEAL 4"	FOOT	96
52000110	PREFORMED JOINT STRIP SEAL	FOOT	116.5
60600505	CONCRETE CURB (SPECIAL)	FOOT	260
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1170
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,250

URBAN
100% State
0014

Pay Item	Description	Unit	Quantity
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5750
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1187.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1187.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7094
78300100	PAVEMENT MARKING REMOVAL	SQ FT	760
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1566
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	10
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	109
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	96
Z0024476	FLEXIBLE DELINEATOR MAINTENANCE	EACH	150
Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1
Z0030370	IMPACT ATTENUATORS, RELOCATE (SEVERE USE, NARROW), TEST LEVEL 3	EACH	1

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISED -
Q:\BRY\CADD plans\Rock Island County\0810247\2010\0810047.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50,0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Fri Dec 10 10:31:25 2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

*Specialty Items

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5834	(115BR)M	Rock Island	22	3

CONTRACT NO. 64G70
ILLINOIS FED. AID PROJECT