

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	100% STATE
				STRUCTURE	
				0014	
				RURAL	
31101200	SUB BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	104		104
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	348		348
50102400	CONCRETE REMOVAL	CU YD	17.4		17.4
50157300	PROTECTIVE SHIELD	SQ YD	1075		1075
50300255	CONCRETE SUPERSTRUCTURE	CU YD	17.4		17.4
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4010		4010
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3970		3970
50800515	BAR SPLICERS	EACH	56		56
52000110	PREFORMED JOINT STRIP SEAL	FOOT	156		156
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	22		22
52100520	ANCHOR BOLTS, 1"	EACH	44		44
58700300	CONCRETE SEALER	SQ FT	22212		22212
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	348		348
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	940		940
67100100	MOBILIZATION	L SUM	1		1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20		20
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4271		4271
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1392		1392
78300100	PAVEMENT MARKING REMOVAL	SQ FT	680		680
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	940		940
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	1492		1492
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	373		373
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	22		22
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	152		152
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	93		93

• SPECIALITY ITEMS

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RLW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr\pwwork\pwwdot\woodshankr1\d0143164	MAIN1-0366A27-details.dgn	DRAWN - RLW	REVISED -			2370	(78-1HB-1)I	PUTNAM	18	3	
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 66A27					
	PLOT DATE = Dec 15, 2010 - 11:05:00 AM	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

Rev.