

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	
				100% STATE	
				STRUCTURE	
				0014	
				RURAL	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	134		134
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SO YD	396		396
50102400	CONCRETE REMOVAL	CU YD	39		39
50300255	CONCRETE SUPERSTRUCTURE	CU YD	39		39
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7880		7880
50800515	BAR SPLICERS	EACH	46		46
52000110	PREFORMED JOINT STRIP SEAL	FOOT	116		116
58700300	CONCRETE SEALER	SO FT	7305		7305
67100100	MOBILIZATION	L SUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350		350
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350		350
* 78001110	PAINT PAVEMENT MARKING - LINE 4 "	FOOT	802		802
* 78001130	PAINT PAVEMENT MARKING - LINE 6 "	FOOT	190		190
78300100	PAVEMENT MARKING REMOVAL	SO FT	645		645
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SO FT	6		6
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1		1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0064600	SELECTIVE CLEARING	ACRE	0.4		0.4

* SPECIALITY ITEMS

Rev.