

GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

SILANE SURFACE SEALER SHALL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS TO THE AREAS DESIGNATED FOR "DECK SLAB REPAIRS".

THE EXISTING VAULTED ABUTMENTS OF THE STRUCTURE ARE CONSIDERED "CONFINED SPACES". THE CONTRACTOR SHALL TAKE APPROPRIATE PRECAUTIONS TO DEAL WITH CONFINED SPACES.

THE COST OF ANY SAW CUTS MADE TO COMPLETE THE WORK AS DESCRIBED IN PLAN DETAILS, UNLESS OTHERWISE NOTED SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED WITH THE VARIOUS PAY REMOVAL PAY ITEMS INVOLVED.

THE WORK REQUIRED TO CONNECT ANY SEWER TO AN EXISTING DRAINAGE STRUCTURE OR PIPE WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICE BID FOR THE SEWER ITEMS.

BEFORE ORDERING PIPE CULVERTS OR PIPE DRAINS, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR EXACT LENGTHS.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE FOLLOWING RATES OF APPLICATIONS HAVE BEEN USED IN CALCULATING PLAN QUANTITIES.

GRANULAR MATERIALS	2.05	TONS/CU YD
--------------------	------	------------

DATE: 12-21-10
 PREPARED BY: Dave Brownak, esr
 DISTRICT STUDIES & PLANS ENGINEER
 EXAMINED BY: Herbert Perry, esr
 DISTRICT CONSTRUCTION ENGINEER
Ray J. Kelly
 DISTRICT MATERIALS ENGINEER
Samuel A. Wheeler
 DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED - -----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\woodshankr1\d8143143\MAIN11-D366A56-details.dgn	DRAWN - RON WOODSHANK	REVISED - -----	68			(IZRI)-2	LASALLE	23	2	
PLOT SCALE = 100.0000' / IN.	CHECKED - ----	REVISED - -----	CONTRACT NO. 66A56							
PLOT DATE = Dec 20, 2010 - 12:40:30 PM	DATE - -----	REVISED - -----	ILLINOIS FED. AID PROJECT							
				SCALE: 50	SHEET NO. 1 OF 1 SHEETS	STA. ----- TO STA. -----				