

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	
				100% STATE ROADWAY	100% STATE STRUCTURE
				PPS #0-01717-3018	PPS #0-01717-3012
				0005 URBAN	0014 URBAN
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	367	367	
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	89	89	
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	101	101	
44213100	PAVEMENT FABRIC	SQ YD	103	103	
44213200	SAW CUTS	FOOT	3222	3222	
50102400	CONCRETE REMOVAL	CU YD	0.2		0.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	0.2		0.2
51100100	SLOPE WALL 4 INCH	SQ YD	8		8
58700300	CONCRETE SEALER	SQ FT	6684		6684
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	47		47
67100100	MOBILIZATION	L SUM	1	0.25	0.75
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	27	5	22
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	38	38	
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	68	68	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	350	350	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	655	655	
* 87900100	DRILL EXISTING FOUNDATION	EACH	1	1	
* 87900200	DRILL EXISTING HANDHOLE	EACH	8	8	
* 88500100	INDUCTION LOOP DETECTOR	EACH	6	6	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	521	521	
50104650	SLOPE WALL REMOVAL	SQ YD	8		8
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	1	

*SPECIALITY ITEM

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED - -----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pw\work\pwwid\woodshankr1\d0143143\MAIN1-0366A56-details.dgn	DRAWN - RON WOODSHANK	REVISED - -----	68			(12R)-2	LASALLE	23	3	
PLOT SCALE = 100.0000' / IN.	CHECKED - -----	REVISED - -----	CONTRACT NO. 66A56							
PLOT DATE = Dec 21, 2010 - 12:47:02 PM	DATE - -----	REVISED - -----	ILLINOIS FED. AID PROJECT							
				SCALE: _____ SHEET NO. 1 OF 2 SHEETS STA. _____ TO STA. _____						

Rev.